


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING				FORM 3 AMENDED REPORT <input checked="" type="checkbox"/>		
APPLICATION FOR PERMIT TO DRILL				1. WELL NAME and NUMBER BONANZA 1023-6A3DS		
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				3. FIELD OR WILDCAT NATURAL BUTTES		
4. TYPE OF WELL Gas Well Coalbed Methane Well: NO				5. UNIT or COMMUNITIZATION AGREEMENT NAME		
6. NAME OF OPERATOR KERR-MCGEE OIL & GAS ONSHORE, L.P.				7. OPERATOR PHONE 720 929-6007		
8. ADDRESS OF OPERATOR P.O. Box 173779, Denver, CO, 80217				9. OPERATOR E-MAIL Kathy.SchneebeckDulnoan@anadarko.com		
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU33433		11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		
13. NAME OF SURFACE OWNER (if box 12 = 'fee')				14. SURFACE OWNER PHONE (if box 12 = 'fee')		
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')				16. SURFACE OWNER E-MAIL (if box 12 = 'fee')		
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')		18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input checked="" type="checkbox"/> (Submit Commingling Application) NO <input type="checkbox"/>		19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>		
20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	2191 FNL 624 FEL	SENE	6	10.0 S	23.0 E	S
Top of Uppermost Producing Zone	1095 FNL 800 FEL	NENE	6	10.0 S	23.0 E	S
At Total Depth	1095 FNL 800 FEL	NENE	6	10.0 S	23.0 E	S
21. COUNTY UINTAH		22. DISTANCE TO NEAREST LEASE LINE (Feet) 800		23. NUMBER OF ACRES IN DRILLING UNIT 1922		
		25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 566		26. PROPOSED DEPTH MD: 8725 TVD: 8550		
27. ELEVATION - GROUND LEVEL 5208		28. BOND NUMBER WYB000291		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Permit #43-8496		
ATTACHMENTS						
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES						
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER			<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN			
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)			<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER			
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)			<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP			
NAME Gina Becker		TITLE Regulatory Analyst II		PHONE 720 929-6086		
SIGNATURE		DATE 01/04/2011		EMAIL gina.becker@anadarko.com		
API NUMBER ASSIGNED 43047514590000		APPROVAL  Permit Manager				

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	4.5	0	8725		
Pipe	Grade	Length	Weight			
	Grade I-80 Buttress	0	11.6			

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	11	8.625	0	2130		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	0	28.0			

Kerr-McGee Oil & Gas Onshore. L.P.**BONANZA 1023-6A3DS**

Surface: 2191 FNL / 624 FEL SENE
 BHL: 1095 FNL / 800 FEL NENE Lot 1

Section 6 T10S R23E

Unitah, Utah
 Mineral Lease: UTU-33433

ONSHORE ORDER NO. 1**DRILLING PROGRAM**

1. & 2. **Estimated Tops of Important Geologic Markers:**
Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1248	
Birds Nest	1522	Water
Mahogany	1882	Water
Wasatch	4272	Gas
Mesaverde	6388	Gas
MVU2	7367	Gas
MVL1	7929	Gas
TVD	8550	
MD	8725	

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Drilling Program

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

6. **Evaluation Program:**

Please refer to the attached Drilling Program

7. **Abnormal Conditions:**

Maximum anticipated bottom hole pressure calculated at 8,550' TVD, approximately equals 5,238 psi (calculated at 0.61 psi/foot).

Maximum anticipated surface pressure equals approximately 3,357 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please refer to the attached Drilling Program.

Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- *Blowout Prevention Equipment (BOPE) requirements;*
- *Mud program requirements; and*
- *Special drilling operation (surface equipment placement) requirements associated with air drilling.*

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). The air rig operation utilizes a 5M BOPE when drilling. This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


10. Other Information:

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP					DATE	December 29, 2010		
WELL NAME	BONANZA 1023-6A3DS					TD	8,550'	TVD	8,725' MD
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah	FINISHED ELEVATION		5,207'
SURFACE LOCATION	SENE	2191 FNL	624 FEL	Sec 6	T 10S	R 23E	Lot 1		
	Latitude: 39.979229		Longitude: -109.362350		NAD 83				
BTM HOLE LOCATION	SWNENE	1095 FNL	800 FEL	Sec 6	T 10S	R 23E			
	Latitude: 39.982236		Longitude: -109.362980		NAD 83				
OBJECTIVE ZONE(S)	Wasatch/Mesaverde								
ADDITIONAL INFO	Regulatory Agencies: BLM (Minerals), BLM (Surface), UDOGM Tri-County Health Dept.								





KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				3,390	1,880	348,000
SURFACE	8-5/8"	0 to 2,130	28.00	IJ-55	LTC	0.96	1.89	5.78
						7,780	6,350	278,000
PRODUCTION	4-1/2"	0 to 8,725	11.60	I-80	BTC	2.25	1.19	3.15

*Burst on surface casing is controlled by fracture gradient as shoe with gas gradient above.

D.F. = 2.53

1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)

(Burst Assumptions: TD = 12.0 ppg)

0.22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MASP 3,357 psi

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

(Burst Assumptions: TD = 12.0 ppg)

0.61 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MABHP 5,238 psi

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
			+ 0.25 pps flocele				
Option 1							
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE			NOTE: If well will circulate water to surface, option 2 will be utilized				
Option 2	LEAD	1,630'	65/35 Poz + 6% Gel + 10 pps gilsonite	150	35%	11.00	3.82
			+ 0.25 pps Flocele + 3% salt BWOW				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	3,765'	Premium Lite II +0.25 pps	270	10%	11.00	3.38
			celloflake + 5 pps gilsonite + 10% gel				
			+ 0.5% extender				
	TAIL	4,960'	50/50 Poz/G + 10% salt + 2% gel	960	10%	14.30	1.31
			+ 0.1% R-3				

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Emile Goodwin / Perry Daughtrey


DATE:

DRILLING SUPERINTENDENT:


John Merkel / Lovel Young

DATE:

EXHIBIT A
BONANZA 1023-6A3DS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK


T10S, R23E, S.L.B.&M.**NOTES:**

- ▲ = Section Corners Located
- 1. Well footages are measured at right angles to the Section Lines.
- 2. G.L.O. distances are shown in feet or chains.
1 chain = 66 feet.
- 3. The Bottom of hole bears N09°13'07"W 1110.02' from the Surface Position.
- 4. Bearings are based on Global Positioning Satellite observations.
- 5. Basis of elevation is Tri-Sta "Two Water" located in the NW ¼ of Section 1, T10S, R21E, S.L.B.&M. The elevation of this Tri-Sta is shown on the Big Pack Mtn NE 7.5 Min. Quadrangle as being 5238'.


Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - BONANZA 1023-6H

BONANZA 1023-6A3DS
WELL PLAT
1095' FNL, 800' FEL (Bottom Hole)
LOT 1 OF SECTION 6, T10S, R23E,
S.L.B.&M., UTAH COUNTY, UTAH.



609 CONSULTING, LLC
371 Coffeen Avenue
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

**SURVEYOR'S CERTIFICATE**

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

John R. Blaug
No. 6028691
JOHN R. BLAUG
PROFESSIONAL LAND SURVEYOR
REGISTRATION No. 6028691
STATE OF UTAH

TIMBERLINE


(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE SURVEYED: 3-3-10	SURVEYED BY: K.B.C.	SHEET NO:
DATE DRAWN: 3-4-10	DRAWN BY: M.W.W.	4
SCALE: 1" = 1000'	Date Last Revised:	4 OF 17

WELL NAME	SURFACE POSITION					BOTTOM HOLE				
	NAD83		NAD27		FOOTAGES	NAD83		NAD27		FOOTAGES
	LATITUDE	LONGITUDE	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	LATITUDE	LONGITUDE	
BONANZA 1023-6G1DS	39°58'45.208"	109°21'44.848"	39°58'45.331"	109°21'42.402"	2193' FNL	39°58'47.604"	109°21'55.905"	39°58'47.727"	109°21'53.459"	1950' FNL
BONANZA 1023-6I2AS	39°58'45.214"	109°21'44.719"	39°58'45.337"	109°21'42.273"	654' FEL	39°58'40.394"	109°21'48.540"	39°58'40.517"	109°21'46.094"	2622' FSL
BONANZA 1023-6H2CS	39°58'45.219"	109°21'44.591"	39°58'45.342"	109°21'42.145"	2192' FNL	39°58'49.027"	109°21'49.549"	39°58'49.150"	109°21'47.103"	1806' FNL
BONANZA 1023-6A3DS	39°58'45.224"	109°21'44.462"	39°58'45.347"	109°21'42.016"	2191' FNL	39°58'56.051"	109°21'46.730"	39°58'56.175"	109°21'44.283"	1095' FNL
BONANZA 1023-6H1BS	39°58'45.229"	109°21'44.335"	39°58'45.352"	109°21'41.889"	2191' FNL	39°58'51.151"	109°21'44.234"	39°58'51.274"	109°21'41.788"	1591' FNL
BONANZA 1023-6H	39°58'45.234"	109°21'44.206"	39°58'45.357"	109°21'41.760"	2190' FNL	39°58'47.604"	109°21'55.905"	39°58'47.727"	109°21'53.459"	1950' FNL

RELATIVE COORDINATES - From Surface Position to Bottom Hole											
WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST
BONANZA 1023-6G1DS	241.5'	-861.3'	BONANZA 1023-6I2AS	-488.2'	-297.0'	BONANZA 1023-6H2CS	385.0'	-386.5'	BONANZA 1023-6A3DS	1095.7'	-177.8'
WELL NAME	NORTH	EAST									
BONANZA 1023-6H1BS	599.4'	7.2'									



Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - BONANZA 1023-6H

WELL PAD INTERFERENCE PLAT
WELLS - BONANZA 1023-6G1DS,
BONANZA 1023-6I2AS, BONANZA 1023-6H2CS,
BONANZA 1023-6A3DS & BONANZA 1023-6H1BS
LOCATED IN SECTION 6, T10S, R23E,
S.L.B.&M., UINTAH COUNTY, UTAH.



CONSULTING, LLC
371 Coffeen Avenue
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE


ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365


DATE SURVEYED: 3-3-10	SURVEYED BY: K.B.C.	SHEET NO: 6 6 OF 17
DATE DRAWN: 3-4-10	DRAWN BY: M.W.W.	
SCALE: 1" = 60'	Date Last Revised:	

[illegible]

Scale: 1"=60'	Date: 4/7/10	SHEET NO: 7 7 OF 17
REVISED: JFE 8/6/10		



CROSS SECTION A-A'



CROSS SECTION B-B'

NOTE: CROSS SECTION B-B' DEPICTS
MAXIMUM RESERVE PIT DEPTH.

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - BONANZA 1023-6H


WELL PAD - CROSS SECTIONS
BONANZA 1023-6G1DS,
BONANZA 1023-6I2AS, BONANZA 1023-6H2CS,
BONANZA 1023-6A3DS & BONANZA 1023-6H1BS
LOCATED IN SECTION 6, T10S, R23E,
S.L.B.&M., UTAH COUNTY, UTAH



CONSULTING, LLC
371 Coffeen Avenue
Sheridan, WY 82801
Phone 307-674-0609
Fax 307-674-0182


TIMBERLINE
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365



Scale: 1"=100'	Date: 4/7/10	SHEET NO:
REVISED:	JFE 8/6/10	8 8 OF 17

'APIWellNo:43047514590000'
C:\NA\BARK\030712\43047514590000.dwg, 8/5/2010 11:46:05 PM






PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE

CAMERA ANGLE: NORTHERLY



PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: NORTHEASTERLY

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - BONANZA 1023-6H

LOCATION PHOTOS
BONANZA 1023-6G1DS,
BONANZA 1023-6I2AS, BONANZA 1023-6H2CS,
BONANZA 1023-6A3DS & BONANZA 1023-6H1BS
LOCATED IN SECTION 6, T10S, R23E,
S.L.B.&M., UINTAH COUNTY, UTAH.




CONSULTING, LLC
371 Coffeen Avenue
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE

(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE PHOTOS TAKEN: 3-3-10	PHOTOS TAKEN BY: K.B.C.	SHEET NO: 10 10 OF 17
DATE DRAWN: 3-4-10	DRAWN BY: M.W.W.	
Date Last Revised:		



Legend

- Proposed Well Location
- Natural Buttes Unit Boundary
- Access Route - Proposed

Distance From Well Pad - BONANZA 1023-6H To Unit Boundary: ±4,583ft

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - BONANZA 1023-6H

TOPO A
BONANZA 1023-6G1DS,
BONANZA 1023-6I2AS, BONANZA 1023-6H2CS,
BONANZA 1023-6A3DS & BONANZA 1023-6H1BS
LOCATED IN SECTION 6, T10S, R23E
S.L.B.&M., UTAH COUNTY, UTAH




Scale: 1:100,000	NAD83 USP Central
Drawn: CPS	Date: 14 Apr 2010
Revised: JID	Date: 6 Aug 2010

Sheet No:

11

11 of 17

Scale: 1" = 2,000ft	NAD83 USP Central	Sheet No:
Drawn: CPS	Date: 14 Apr 2010	12 12 of 17
Revised: JID	Date: 6 Aug 2010	



Proposed Well	Nearest Well Bore	Footage
BONANZA 1023-6G1DS	BONANZA 1023-6G	783ft
BONANZA 1023-6I2AS	BONANZA 1023-6H	595ft
BONANZA 1023-6H2CS	BONANZA 1023-6H	566ft
BONANZA 1023-6A3DS	BONANZA 1023-6A	770ft
BONANZA 1023-6H1BS	BONANZA 1023-6H	599ft

Legend

- Well - Proposed
- Bottom Hole - Proposed
- Well Path
- Well Pad
- Well - 1 Mile Radius

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - BONANZA 1023-6H


TOPO C
BONANZA 1023-6G1DS,
BONANZA 1023-6I2AS, BONANZA 1023-6H2CS,
BONANZA 1023-6A3DS & BONANZA 1023-6H1BS
LOCATED IN SECTION 6, T10S, R23E
S.L.B.&M., UINTAH COUNTY, UTAH

609
CONSULTING, LLC
371 Coffeen Avenue
Sheridan, WY 82801
Phone (307) 674-0609
Fax (307) 674-0182



- Producing
- Temporarily-Abandoned
- Shut-In
- Plugged and Abandoned
- Location Abandoned
- Dry hole marker, buried
- Returned APD (Unapproved)
- Active
- Spudded (Drilling commenced; Not yet completed)
- Approved permit (APD); not yet spudded
- New Permit (Not yet approved or drilled)
- Inactive
- Drilling Operations Suspended

Scale: 1" = 2,000ft | NAD83 USP Central | Sheet No: **13** 13 of 17
Drawn: CPS | Date: 14 Apr 2010
Revised: JID | Date: 6 Aug 2010



Proposed Liquid Pipeline	Length
Proposed 6" (First Meter House to Edge of Pad)	±450ft
Proposed 6" (Edge of Pad to 5M Pad)	±5,350ft
TOTAL PROPOSED LIQUID PIPELINE =	±5,800ft

Proposed Gas Pipeline	Length
Proposed 6" (First Meter House to Edge of Pad)	±450ft
Proposed 6" (Edge of Pad to 5L Intersection)	±160ft
Proposed 10" (5L Intersection to Proposed 16" Pipeline)	±1,270ft
Proposed 16" (Proposed 16" Pipeline to 5M Intersection)	±3,640ft
TOTAL PROPOSED GAS PIPELINE =	±4,620ft

Legend

- Well - Proposed
 --- Gas Pipeline - Proposed
 --- Liquid Pipeline - Proposed
 --- Road - Proposed
 Bureau of Land Management
- Well - Existing
 --- Gas Pipeline - To Be Upgraded
 --- Liquid Pipeline - To Be Upgraded
 --- Road - Existing
 Indian Reservation
- Well Pad
 --- Gas Pipeline - Existing
 --- Liquid Pipeline - Existing
 State
 Private

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202


WELL PAD - BONANZA 1023-6H

TOPO D
BONANZA 1023-6G1DS,
BONANZA 1023-6I2AS, BONANZA 1023-6H2CS,
BONANZA 1023-6A3DS & BONANZA 1023-6H1BS
 LOCATED IN SECTION 6, T10S, R23E
 S.L.B.&M., UINTAH COUNTY, UTAH

609
CONSULTING, LLC
 371 Coffeen Avenue
 Sheridan, WY 82801
 Phone (307) 674-0609
 Fax (307) 674-0182



Scale: 1" = 2,000ft	NAD83 USP Central	Sheet No:
Drawn: CPS	Date: 14 Apr 2010	14
Revised: CPS	Date: 15 Oct 2010	



Proposed Liquid Pipeline	Length
Proposed 6" (First Meter House to Edge of Pad)	±450ft
Proposed 6" (Edge of Pad to 5M Pad)	±5,350ft
TOTAL PROPOSED LIQUID PIPELINE =	±5,800ft

Proposed Gas Pipeline	Length
Proposed 6" (First Meter House to Edge of Pad)	±450ft
Proposed 6" (Edge of Pad to 5L Intersection)	±160ft
Proposed 10" (5L Intersection to Proposed 16" Pipeline)	±1,270ft
Proposed 16" (Proposed 16" Pipeline to 5M Intersection)	±3,640ft
TOTAL PROPOSED GAS PIPELINE =	±4,620ft

Legend

- Well - Proposed
- Well - Existing
- Well Pad
- - - Gas Pipeline - Proposed
- - - Gas Pipeline - To Be Upgraded
- Gas Pipeline - Existing
- - - Liquid Pipeline - Proposed
- - - Liquid Pipeline - To Be Upgraded
- Liquid Pipeline - Existing
- Road - Proposed
- Road - Existing
- Bureau of Land Management
- Indian Reservation
- State
- Private

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - BONANZA 1023-6H

TOPO D2 (PAD & PIPELINE DETAIL)
BONANZA 1023-6G1DS,
BONANZA 1023-6I2AS, BONANZA 1023-6H2CS,
BONANZA 1023-6A3DS & BONANZA 1023-6H1BS
LOCATED IN SECTION 6, T10S, R23E
S.L.B.&M., UINTAH COUNTY, UTAH




Scale: 1" = 1,000ft
NAD83 USP Central
Drawn: CPS
Revised: CPS

Sheet No:

15
15 of 17

Date: 14 Apr 2010
Date: 14 Oct 2010



Proposed Well	Distance to Nearest CA Boundary
BONANZA 1023-6G1DS	1,126ft
BONANZA 1023-6I2AS	942ft
BONANZA 1023-6H2CS	1,020ft
BONANZA 1023-6A3DS	800ft
BONANZA 1023-6H1BS	606ft

Proposed Well	Distance To Nearest Lease Boundary
BONANZA 1023-6G1DS	194ft
BONANZA 1023-6I2AS	19ft
BONANZA 1023-6H2CS	301ft
BONANZA 1023-6A3DS	576ft
BONANZA 1023-6H1BS	715ft

Legend

Well - Proposed	Well Pad	Gas Pipeline - Proposed	Liquid Pipeline - Proposed	Road - Proposed	Bureau of Land Management
Bottom Hole - Proposed	Lease Boundary	Gas Pipeline - To Be Upgraded	Liquid Pipeline - To Be Upgraded	Road - Existing	Indian Reservation
Well Path	CA Agreement	Gas Pipeline - Existing	Liquid Pipeline - Existing		State
					Private

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - BONANZA 1023-6H

TOPO E
BONANZA 1023-6G1DS,
BONANZA 1023-6I2AS, BONANZA 1023-6H2CS,
BONANZA 1023-6A3DS & BONANZA 1023-6H1BS
LOCATED IN SECTION 6, T10S, R23E
S.L.B.&M., UINTAH COUNTY, UTAH



Scale: 1" = 2,000ft	NAD83 USP Central	Sheet No:
Drawn: CPS	Date: 14 Apr 2010	16 16 of 17
Revised: CPS	Date: 15 Oct 2010	




**Kerr-McGee Oil & Gas Onshore, LP
WELL PAD – BONANZA 1023-6H
WELLS – BONANZA 1023-6G1DS, BONANZA 1023-6I2AS,
BONANZA 1023-6H2CS, BONANZA 1023-6A3DS &
BONANZA 1023-6H1BS
Section 6, T10S, R23E, S.L.B.&M.**

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah proceed in an easterly then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45; exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 14.4 miles to the intersection of the Chipeta Wells Road (County B Road 3410) which road intersection is approximately 400 feet northeast of the Mountain Fuel Bridge, at the White River. Exit left and proceed in a southeasterly direction along the Chipeta Wells Road approximately 4.3 miles to the intersection of the Atchee Wash Road (County B Road 4240). Exit right and proceed in a southeasterly, then southerly direction along the Atchee Wash Road approximately 4.0 miles to a service road to the left. Exit left and proceed in a southeasterly direction along service road approximately 1.0 miles to a second service road to the left. Exit left and proceed in a northeasterly direction along service road approximately 0.2 miles to the proposed access road. Follow the road flags in a northeasterly direction approximately 100 feet to the proposed well pad.

Total distance from Vernal, Utah to the proposed well location is approximately 47.4 miles in a southerly direction.

WELL DETAILS: BONANZA 1023-6A3DS					
GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)					
+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	14522710.16	2099394.11	39° 58' 45.347 N	109° 21' 42.016 W

DESIGN TARGET DETAILS							
Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
PBHL	8550.00	1095.58	-176.52	14523802.31	2099197.49	39° 58' 56.176 N	109° 21' 44.284 W
- plan hits target center							
Shape							
Circle (Radius: 25.00)							



SECTION DETAILS										
MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Target	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00		
1300.00	20.00	350.85	1279.82	170.57	-27.48	2.00	350.85	172.77		
3534.29	20.00	350.85	3379.36	925.01	-149.04	0.00	0.00	936.94		
4534.29	0.00	0.00	4359.18	1095.58	-176.52	2.00	180.00	1109.71		
8725.11	0.00	0.00	8550.00	1095.58	-176.52	0.00	0.00	1109.71	BONANZA 1023-6A3DS PBHL	

PROJECT DETAILS: Uintah County, UT UTM12				FORMATION TOP DETAILS		
Geodetic System: Universal Transverse Mercator (US Survey Feet)				TVDPath	MDPath	Formation
Datum: NAD 1927 - Western US				1248.00	1266.21	GREEN RIVER
Ellipsoid: Clarke 1866				4272.00	4447.10	WASATCH
Zone: Zone 12N (114 W to 108 W)				6388.00	6563.11	MESAVERDE
Location: SEC 6 T10S R23E						
System Datum: Mean Sea Level						

CASING DETAILS					
TVD	MD	Name	Size		
2332.00	2419.71	8 5/8"	8.625		

Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12

Bonanza 1023-6H PAD

BONANZA 1023-6A3DS

OH

Plan: PLAN #1

Standard Planning Report

09 September, 2010

Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well BONANZA 1023-6A3DS
Company:	Kerr McGee Oil and Gas Onshore LP	TVD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	MD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Site:	Bonanza 1023-6H PAD	North Reference:	True
Well:	BONANZA 1023-6A3DS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1		

Project	Uintah County, UT UTM12		
Map System:	Universal Transverse Mercator (US Survey Feet)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 - Western US		
Map Zone:	Zone 12N (114 W to 108 W)		

Site		Bonanza 1023-6H PAD, SEC 6 T10S R23E			
Site Position:		Northing:	14,522,708.16 usft	Latitude:	39° 58' 45.332 N
From:	Lat/Long	Easting:	2,099,364.16 usft	Longitude:	109° 21' 42.401 W
Position Uncertainty:	0.00 ft	Slot Radius:	13.200 in	Grid Convergence:	1.05 °

Well	BONANZA 1023-6A3DS, 2192' FNL 624' FEL					
Well Position	+N/-S	1.46 ft	Northing:	14,522,710.16 usft	Latitude:	39° 58' 45.347 N
	+E/-W	29.98 ft	Easting:	2,099,394.11 usft	Longitude:	109° 21' 42.016 W
Position Uncertainty		0.00 ft	Wellhead Elevation:		Ground Level:	5,207.00 ft

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	09/09/2010	11.11	65.90	52,411

Design	PLAN #1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	350.85

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,300.00	20.00	350.85	1,279.82	170.57	-27.48	2.00	2.00	0.00	350.85	
3,534.29	20.00	350.85	3,379.36	925.01	-149.04	0.00	0.00	0.00	0.00	
4,534.29	0.00	0.00	4,359.18	1,095.58	-176.52	2.00	-2.00	0.00	180.00	
8,725.11	0.00	0.00	8,550.00	1,095.58	-176.52	0.00	0.00	0.00	0.00	BONANZA 1023-6A3I

Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well BONANZA 1023-6A3DS
Company:	Kerr McGee Oil and Gas Onshore LP	TVD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	MD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Site:	Bonanza 1023-6H PAD	North Reference:	True
Well:	BONANZA 1023-6A3DS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00	
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
Start Build 2.00										
400.00	2.00	350.85	399.98	1.72	-0.28	1.75	2.00	2.00	0.00	
500.00	4.00	350.85	499.84	6.89	-1.11	6.98	2.00	2.00	0.00	
600.00	6.00	350.85	599.45	15.49	-2.50	15.69	2.00	2.00	0.00	
700.00	8.00	350.85	698.70	27.52	-4.43	27.88	2.00	2.00	0.00	
800.00	10.00	350.85	797.47	42.97	-6.92	43.52	2.00	2.00	0.00	
900.00	12.00	350.85	895.62	61.81	-9.96	62.60	2.00	2.00	0.00	
1,000.00	14.00	350.85	993.06	84.01	-13.54	85.10	2.00	2.00	0.00	
1,100.00	16.00	350.85	1,089.64	109.56	-17.65	110.98	2.00	2.00	0.00	
1,200.00	18.00	350.85	1,185.27	138.43	-22.30	140.21	2.00	2.00	0.00	
1,266.21	19.32	350.85	1,248.00	159.34	-25.67	161.40	2.00	2.00	0.00	
GREEN RIVER										
1,300.00	20.00	350.85	1,279.82	170.57	-27.48	172.77	2.00	2.00	0.00	
Start 2234.29 hold at 1300.00 MD										
1,400.00	20.00	350.85	1,373.78	204.33	-32.92	206.97	0.00	0.00	0.00	
1,500.00	20.00	350.85	1,467.75	238.10	-38.36	241.17	0.00	0.00	0.00	
1,600.00	20.00	350.85	1,561.72	271.87	-43.80	275.37	0.00	0.00	0.00	
1,700.00	20.00	350.85	1,655.69	305.63	-49.25	309.58	0.00	0.00	0.00	
1,800.00	20.00	350.85	1,749.66	339.40	-54.69	343.78	0.00	0.00	0.00	
1,900.00	20.00	350.85	1,843.63	373.17	-60.13	377.98	0.00	0.00	0.00	
2,000.00	20.00	350.85	1,937.60	406.93	-65.57	412.18	0.00	0.00	0.00	
2,100.00	20.00	350.85	2,031.57	440.70	-71.01	446.38	0.00	0.00	0.00	
2,200.00	20.00	350.85	2,125.54	474.47	-76.45	480.59	0.00	0.00	0.00	
2,300.00	20.00	350.85	2,219.51	508.23	-81.89	514.79	0.00	0.00	0.00	
2,400.00	20.00	350.85	2,313.48	542.00	-87.33	548.99	0.00	0.00	0.00	
2,419.71	20.00	350.85	2,332.00	548.66	-88.40	555.73	0.00	0.00	0.00	
8 5/8"										
2,500.00	20.00	350.85	2,407.45	575.77	-92.77	583.19	0.00	0.00	0.00	
2,600.00	20.00	350.85	2,501.42	609.53	-98.21	617.39	0.00	0.00	0.00	
2,700.00	20.00	350.85	2,595.39	643.30	-103.65	651.60	0.00	0.00	0.00	
2,800.00	20.00	350.85	2,689.35	677.07	-109.09	685.80	0.00	0.00	0.00	
2,900.00	20.00	350.85	2,783.32	710.83	-114.53	720.00	0.00	0.00	0.00	
3,000.00	20.00	350.85	2,877.29	744.60	-119.97	754.20	0.00	0.00	0.00	
3,100.00	20.00	350.85	2,971.26	778.37	-125.41	788.40	0.00	0.00	0.00	
3,200.00	20.00	350.85	3,065.23	812.13	-130.85	822.61	0.00	0.00	0.00	
3,300.00	20.00	350.85	3,159.20	845.90	-136.30	856.81	0.00	0.00	0.00	
3,400.00	20.00	350.85	3,253.17	879.66	-141.74	891.01	0.00	0.00	0.00	
3,500.00	20.00	350.85	3,347.14	913.43	-147.18	925.21	0.00	0.00	0.00	
3,534.29	20.00	350.85	3,379.36	925.01	-149.04	936.94	0.00	0.00	0.00	
Start Drop -2.00										
3,600.00	18.69	350.85	3,441.36	946.50	-152.50	958.70	2.00	-2.00	0.00	
3,700.00	16.69	350.85	3,536.63	976.49	-157.34	989.08	2.00	-2.00	0.00	
3,800.00	14.69	350.85	3,632.90	1,003.18	-161.64	1,016.12	2.00	-2.00	0.00	
3,900.00	12.69	350.85	3,730.06	1,026.54	-165.40	1,039.78	2.00	-2.00	0.00	
4,000.00	10.69	350.85	3,827.98	1,046.53	-168.62	1,060.03	2.00	-2.00	0.00	
4,100.00	8.69	350.85	3,926.55	1,063.14	-171.30	1,076.85	2.00	-2.00	0.00	
4,200.00	6.69	350.85	4,025.65	1,076.34	-173.43	1,090.23	2.00	-2.00	0.00	

Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well BONANZA 1023-6A3DS
Company:	Kerr McGee Oil and Gas Onshore LP	TVD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	MD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Site:	Bonanza 1023-6H PAD	North Reference:	True
Well:	BONANZA 1023-6A3DS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,300.00	4.69	350.85	4,125.15	1,086.12	-175.00	1,100.13	2.00	-2.00	0.00
4,400.00	2.69	350.85	4,224.94	1,092.47	-176.02	1,106.56	2.00	-2.00	0.00
4,447.10	1.74	350.85	4,272.00	1,094.27	-176.31	1,108.38	2.00	-2.00	0.00
WASATCH									
4,500.00	0.69	350.85	4,324.89	1,095.38	-176.49	1,109.50	2.00	-2.00	0.00
4,534.29	0.00	0.00	4,359.18	1,095.58	-176.52	1,109.71	2.00	-2.00	0.00
Start 4190.82 hold at 4534.29 MD									
4,600.00	0.00	0.00	4,424.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
4,700.00	0.00	0.00	4,524.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
4,800.00	0.00	0.00	4,624.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
4,900.00	0.00	0.00	4,724.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
5,000.00	0.00	0.00	4,824.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
5,100.00	0.00	0.00	4,924.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
5,200.00	0.00	0.00	5,024.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
5,300.00	0.00	0.00	5,124.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
5,400.00	0.00	0.00	5,224.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
5,500.00	0.00	0.00	5,324.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
5,600.00	0.00	0.00	5,424.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
5,700.00	0.00	0.00	5,524.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
5,800.00	0.00	0.00	5,624.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
5,900.00	0.00	0.00	5,724.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
6,000.00	0.00	0.00	5,824.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
6,100.00	0.00	0.00	5,924.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
6,200.00	0.00	0.00	6,024.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
6,300.00	0.00	0.00	6,124.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
6,400.00	0.00	0.00	6,224.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
6,500.00	0.00	0.00	6,324.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
6,563.11	0.00	0.00	6,388.00	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
MESAVERDE									
6,600.00	0.00	0.00	6,424.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
6,700.00	0.00	0.00	6,524.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
6,800.00	0.00	0.00	6,624.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
6,900.00	0.00	0.00	6,724.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
7,000.00	0.00	0.00	6,824.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
7,100.00	0.00	0.00	6,924.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
7,200.00	0.00	0.00	7,024.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
7,300.00	0.00	0.00	7,124.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
7,400.00	0.00	0.00	7,224.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
7,500.00	0.00	0.00	7,324.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
7,600.00	0.00	0.00	7,424.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
7,700.00	0.00	0.00	7,524.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
7,800.00	0.00	0.00	7,624.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
7,900.00	0.00	0.00	7,724.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
8,000.00	0.00	0.00	7,824.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
8,100.00	0.00	0.00	7,924.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
8,200.00	0.00	0.00	8,024.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
8,300.00	0.00	0.00	8,124.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
8,400.00	0.00	0.00	8,224.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
8,500.00	0.00	0.00	8,324.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
8,600.00	0.00	0.00	8,424.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
8,700.00	0.00	0.00	8,524.89	1,095.58	-176.52	1,109.71	0.00	0.00	0.00
8,725.11	0.00	0.00	8,550.00	1,095.58	-176.52	1,109.71	0.00	0.00	0.00

Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well BONANZA 1023-6A3DS
Company:	Kerr McGee Oil and Gas Onshore LP	TVD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	MD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Site:	Bonanza 1023-6H PAD	North Reference:	True
Well:	BONANZA 1023-6A3DS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
TD at 8725.11 - BONANZA 1023-6A3DS PBHL									

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
BONANZA 1023-6A3DS - plan hits target center - Circle (radius 25.00)	0.00	0.00	8,550.00	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)	
2,419.71	2,332.00	8 5/8"	8.625	11.000	

Formations						
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
1,266.21	1,248.00	GREEN RIVER				
4,447.10	4,272.00	WASATCH				
6,563.11	6,388.00	MESAVERDE				

Plan Annotations				
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
300.00	300.00	0.00	0.00	Start Build 2.00
1,300.00	1,279.82	170.57	-27.48	Start 2234.29 hold at 1300.00 MD
3,534.29	3,379.36	925.01	-149.04	Start Drop -2.00
4,534.29	4,359.18	1,095.58	-176.52	Start 4190.82 hold at 4534.29 MD
8,725.11	8,550.00	1,095.58	-176.52	TD at 8725.11

Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12

Bonanza 1023-6H PAD

BONANZA 1023-6A3DS

OH

Plan: PLAN #1

Standard Planning Report - Geographic

09 September, 2010

Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well BONANZA 1023-6A3DS
Company:	Kerr McGee Oil and Gas Onshore LP	TVD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	MD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Site:	Bonanza 1023-6H PAD	North Reference:	True
Well:	BONANZA 1023-6A3DS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1		

Project	Uintah County, UT UTM12		
Map System:	Universal Transverse Mercator (US Survey Feet)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 - Western US		
Map Zone:	Zone 12N (114 W to 108 W)		

Site	Bonanza 1023-6H PAD, SEC 6 T10S R23E			
Site Position:		Northing:	14,522,708.16 usft	Latitude: 39° 58' 45.332 N
From:	Lat/Long	Easting:	2,099,364.16 usft	Longitude: 109° 21' 42.401 W
Position Uncertainty:	0.00 ft	Slot Radius:	13.200 in	Grid Convergence: 1.05 °

Well	BONANZA 1023-6A3DS, 2192' FNL 624' FEL			
Well Position	+N/-S	0.00 ft	Northing:	14,522,710.16 usft
	+E/-W	0.00 ft	Easting:	2,099,394.11 usft
Position Uncertainty	0.00 ft	Wellhead Elevation:		Ground Level: 5,207.00 ft

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	09/09/2010	11.11	65.90	52,411

Design	PLAN #1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	350.85

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,300.00	20.00	350.85	1,279.82	170.57	-27.48	2.00	2.00	0.00	350.85	
3,534.29	20.00	350.85	3,379.36	925.01	-149.04	0.00	0.00	0.00	0.00	
4,534.29	0.00	0.00	4,359.18	1,095.58	-176.52	2.00	-2.00	0.00	180.00	
8,725.11	0.00	0.00	8,550.00	1,095.58	-176.52	0.00	0.00	0.00	0.00	BONANZA 1023-6A3I

Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well BONANZA 1023-6A3DS
Company:	Kerr McGee Oil and Gas Onshore LP	TVD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	MD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Site:	Bonanza 1023-6H PAD	North Reference:	True
Well:	BONANZA 1023-6A3DS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	14,522,710.16	2,099,394.11	39° 58' 45.347 N	109° 21' 42.016 W
100.00	0.00	0.00	100.00	0.00	0.00	14,522,710.16	2,099,394.11	39° 58' 45.347 N	109° 21' 42.016 W
200.00	0.00	0.00	200.00	0.00	0.00	14,522,710.16	2,099,394.11	39° 58' 45.347 N	109° 21' 42.016 W
300.00	0.00	0.00	300.00	0.00	0.00	14,522,710.16	2,099,394.11	39° 58' 45.347 N	109° 21' 42.016 W
Start Build 2.00									
400.00	2.00	350.85	399.98	1.72	-0.28	14,522,711.88	2,099,393.80	39° 58' 45.364 N	109° 21' 42.019 W
500.00	4.00	350.85	499.84	6.89	-1.11	14,522,717.03	2,099,392.87	39° 58' 45.415 N	109° 21' 42.030 W
600.00	6.00	350.85	599.45	15.49	-2.50	14,522,725.61	2,099,391.33	39° 58' 45.500 N	109° 21' 42.048 W
700.00	8.00	350.85	698.70	27.52	-4.43	14,522,737.60	2,099,389.17	39° 58' 45.619 N	109° 21' 42.073 W
800.00	10.00	350.85	797.47	42.97	-6.92	14,522,753.00	2,099,386.40	39° 58' 45.772 N	109° 21' 42.105 W
900.00	12.00	350.85	895.62	61.81	-9.96	14,522,771.78	2,099,383.02	39° 58' 45.958 N	109° 21' 42.144 W
1,000.00	14.00	350.85	993.06	84.01	-13.54	14,522,793.91	2,099,379.03	39° 58' 46.177 N	109° 21' 42.190 W
1,100.00	16.00	350.85	1,089.64	109.56	-17.65	14,522,819.38	2,099,374.44	39° 58' 46.430 N	109° 21' 42.242 W
1,200.00	18.00	350.85	1,185.27	138.43	-22.30	14,522,848.16	2,099,369.26	39° 58' 46.715 N	109° 21' 42.302 W
1,266.21	19.32	350.85	1,248.00	159.34	-25.67	14,522,869.01	2,099,365.51	39° 58' 46.922 N	109° 21' 42.345 W
GREEN RIVER									
1,300.00	20.00	350.85	1,279.82	170.57	-27.48	14,522,880.20	2,099,363.50	39° 58' 47.033 N	109° 21' 42.369 W
Start 2234.29 hold at 1300.00 MD									
1,400.00	20.00	350.85	1,373.78	204.33	-32.92	14,522,913.86	2,099,357.44	39° 58' 47.366 N	109° 21' 42.439 W
1,500.00	20.00	350.85	1,467.75	238.10	-38.36	14,522,947.52	2,099,351.38	39° 58' 47.700 N	109° 21' 42.508 W
1,600.00	20.00	350.85	1,561.72	271.87	-43.80	14,522,981.18	2,099,345.32	39° 58' 48.034 N	109° 21' 42.578 W
1,700.00	20.00	350.85	1,655.69	305.63	-49.25	14,523,014.84	2,099,339.26	39° 58' 48.368 N	109° 21' 42.648 W
1,800.00	20.00	350.85	1,749.66	339.40	-54.69	14,523,048.50	2,099,333.20	39° 58' 48.701 N	109° 21' 42.718 W
1,900.00	20.00	350.85	1,843.63	373.17	-60.13	14,523,082.16	2,099,327.14	39° 58' 49.035 N	109° 21' 42.788 W
2,000.00	20.00	350.85	1,937.60	406.93	-65.57	14,523,115.82	2,099,321.08	39° 58' 49.369 N	109° 21' 42.858 W
2,100.00	20.00	350.85	2,031.57	440.70	-71.01	14,523,149.48	2,099,315.01	39° 58' 49.703 N	109° 21' 42.928 W
2,200.00	20.00	350.85	2,125.54	474.47	-76.45	14,523,183.14	2,099,308.95	39° 58' 50.036 N	109° 21' 42.998 W
2,300.00	20.00	350.85	2,219.51	508.23	-81.89	14,523,216.81	2,099,302.89	39° 58' 50.370 N	109° 21' 43.068 W
2,400.00	20.00	350.85	2,313.48	542.00	-87.33	14,523,250.47	2,099,296.83	39° 58' 50.704 N	109° 21' 43.138 W
2,419.71	20.00	350.85	2,332.00	548.66	-88.40	14,523,257.10	2,099,295.64	39° 58' 50.770 N	109° 21' 43.151 W
8 5/8"									
2,500.00	20.00	350.85	2,407.45	575.77	-92.77	14,523,284.13	2,099,290.77	39° 58' 51.038 N	109° 21' 43.207 W
2,600.00	20.00	350.85	2,501.42	609.53	-98.21	14,523,317.79	2,099,284.71	39° 58' 51.371 N	109° 21' 43.277 W
2,700.00	20.00	350.85	2,595.39	643.30	-103.65	14,523,351.45	2,099,278.65	39° 58' 51.705 N	109° 21' 43.347 W
2,800.00	20.00	350.85	2,689.35	677.07	-109.09	14,523,385.11	2,099,272.59	39° 58' 52.039 N	109° 21' 43.417 W
2,900.00	20.00	350.85	2,783.32	710.83	-114.53	14,523,418.77	2,099,266.53	39° 58' 52.373 N	109° 21' 43.487 W
3,000.00	20.00	350.85	2,877.29	744.60	-119.97	14,523,452.43	2,099,260.47	39° 58' 52.706 N	109° 21' 43.557 W
3,100.00	20.00	350.85	2,971.26	778.37	-125.41	14,523,486.09	2,099,254.41	39° 58' 53.040 N	109° 21' 43.627 W
3,200.00	20.00	350.85	3,065.23	812.13	-130.85	14,523,519.75	2,099,248.35	39° 58' 53.374 N	109° 21' 43.697 W
3,300.00	20.00	350.85	3,159.20	845.90	-136.30	14,523,553.41	2,099,242.29	39° 58' 53.708 N	109° 21' 43.767 W
3,400.00	20.00	350.85	3,253.17	879.66	-141.74	14,523,587.07	2,099,236.23	39° 58' 54.041 N	109° 21' 43.837 W
3,500.00	20.00	350.85	3,347.14	913.43	-147.18	14,523,620.73	2,099,230.17	39° 58' 54.375 N	109° 21' 43.907 W
3,534.29	20.00	350.85	3,379.36	925.01	-149.04	14,523,632.28	2,099,228.09	39° 58' 54.490 N	109° 21' 43.930 W
Start Drop -2.00									
3,600.00	18.69	350.85	3,441.36	946.50	-152.50	14,523,653.70	2,099,224.24	39° 58' 54.702 N	109° 21' 43.975 W
3,700.00	16.69	350.85	3,536.63	976.49	-157.34	14,523,683.59	2,099,218.86	39° 58' 54.999 N	109° 21' 44.037 W
3,800.00	14.69	350.85	3,632.90	1,003.18	-161.64	14,523,710.20	2,099,214.07	39° 58' 55.262 N	109° 21' 44.092 W
3,900.00	12.69	350.85	3,730.06	1,026.54	-165.40	14,523,733.49	2,099,209.87	39° 58' 55.493 N	109° 21' 44.141 W
4,000.00	10.69	350.85	3,827.98	1,046.53	-168.62	14,523,753.42	2,099,206.28	39° 58' 55.691 N	109° 21' 44.182 W
4,100.00	8.69	350.85	3,926.55	1,063.14	-171.30	14,523,769.98	2,099,203.30	39° 58' 55.855 N	109° 21' 44.216 W
4,200.00	6.69	350.85	4,025.65	1,076.34	-173.43	14,523,783.14	2,099,200.93	39° 58' 55.985 N	109° 21' 44.244 W
4,300.00	4.69	350.85	4,125.15	1,086.12	-175.00	14,523,792.89	2,099,199.18	39° 58' 56.082 N	109° 21' 44.264 W

Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well BONANZA 1023-6A3DS
Company:	Kerr McGee Oil and Gas Onshore LP	TVD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	MD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Site:	Bonanza 1023-6H PAD	North Reference:	True
Well:	BONANZA 1023-6A3DS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
4,400.00	2.69	350.85	4,224.94	1,092.47	-176.02	14,523,799.21	2,099,198.04	39° 58' 56.145 N	109° 21' 44.277 W
4,447.10	1.74	350.85	4,272.00	1,094.27	-176.31	14,523,801.01	2,099,197.72	39° 58' 56.163 N	109° 21' 44.281 W
WASATCH									
4,500.00	0.69	350.85	4,324.89	1,095.38	-176.49	14,523,802.11	2,099,197.52	39° 58' 56.174 N	109° 21' 44.283 W
4,534.29	0.00	0.00	4,359.18	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
Start 4190.82 hold at 4534.29 MD									
4,600.00	0.00	0.00	4,424.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
4,700.00	0.00	0.00	4,524.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
4,800.00	0.00	0.00	4,624.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
4,900.00	0.00	0.00	4,724.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
5,000.00	0.00	0.00	4,824.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
5,100.00	0.00	0.00	4,924.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
5,200.00	0.00	0.00	5,024.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
5,300.00	0.00	0.00	5,124.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
5,400.00	0.00	0.00	5,224.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
5,500.00	0.00	0.00	5,324.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
5,600.00	0.00	0.00	5,424.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
5,700.00	0.00	0.00	5,524.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
5,800.00	0.00	0.00	5,624.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
5,900.00	0.00	0.00	5,724.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
6,000.00	0.00	0.00	5,824.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
6,100.00	0.00	0.00	5,924.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
6,200.00	0.00	0.00	6,024.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
6,300.00	0.00	0.00	6,124.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
6,400.00	0.00	0.00	6,224.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
6,500.00	0.00	0.00	6,324.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
6,563.11	0.00	0.00	6,388.00	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
MESAVERDE									
6,600.00	0.00	0.00	6,424.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
6,700.00	0.00	0.00	6,524.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
6,800.00	0.00	0.00	6,624.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
6,900.00	0.00	0.00	6,724.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
7,000.00	0.00	0.00	6,824.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
7,100.00	0.00	0.00	6,924.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
7,200.00	0.00	0.00	7,024.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
7,300.00	0.00	0.00	7,124.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
7,400.00	0.00	0.00	7,224.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
7,500.00	0.00	0.00	7,324.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
7,600.00	0.00	0.00	7,424.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
7,700.00	0.00	0.00	7,524.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
7,800.00	0.00	0.00	7,624.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
7,900.00	0.00	0.00	7,724.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
8,000.00	0.00	0.00	7,824.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
8,100.00	0.00	0.00	7,924.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
8,200.00	0.00	0.00	8,024.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
8,300.00	0.00	0.00	8,124.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
8,400.00	0.00	0.00	8,224.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
8,500.00	0.00	0.00	8,324.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
8,600.00	0.00	0.00	8,424.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
8,700.00	0.00	0.00	8,524.89	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
8,725.11	0.00	0.00	8,550.00	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W
TD at 8725.11 - BONANZA 1023-6A3DS PBHL									

Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well BONANZA 1023-6A3DS
Company:	Kerr McGee Oil and Gas Onshore LP	TVD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Project:	Uintah County, UT UTM12	MD Reference:	GL 5207' & RKB 14' @ 5221.00ft (ASSUMED)
Site:	Bonanza 1023-6H PAD	North Reference:	True
Well:	BONANZA 1023-6A3DS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1		

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
BONANZA 1023-6A3DS - plan hits target center - Circle (radius 25.00)	0.00	0.00	8,550.00	1,095.58	-176.52	14,523,802.31	2,099,197.48	39° 58' 56.176 N	109° 21' 44.284 W

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)	
2,419.71	2,332.00	8 5/8"	8.625	11.000	

Formations					
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,266.21	1,248.00	GREEN RIVER			
4,447.10	4,272.00	WASATCH			
6,563.11	6,388.00	MESAVERDE			

Plan Annotations				
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
300.00	300.00	0.00	0.00	Start Build 2.00
1,300.00	1,279.82	170.57	-27.48	Start 2234.29 hold at 1300.00 MD
3,534.29	3,379.36	925.01	-149.04	Start Drop -2.00
4,534.29	4,359.18	1,095.58	-176.52	Start 4190.82 hold at 4534.29 MD
8,725.11	8,550.00	1,095.58	-176.52	TD at 8725.11

Bonanza 1023-6A3DS/ 1023-6G1DS/ 1023-6H1BS/ 1023-6H2CS/
1023-6I2AS
Kerr-McGee Oil Gas Onshore, L.P.

Bonanza 1023-6H Pad
Surface Use Plan of Operations
1 of 10

Kerr-McGee Oil & Gas Onshore. L.P.

Bonanza 1023-6H Pad

<u>API #</u>	<u>BONANZA 1023-6A3DS</u>		
	Surface: 2191 FNL / 624 FEL	SENE	Lot
	BHL: 1095 FNL / 800 FEL	NENE	Lot 1
<u>API #</u>	<u>BONANZA 1023-6G1DS</u>		
	Surface: 2193 FNL / 654 FEL	SENE	Lot
	BHL: 1950 FNL / 1515 FEL	SWNE	Lot
<u>API #</u>	<u>BONANZA 1023-6H1BS</u>		
	Surface: 2191 FNL / 614 FEL	SENE	Lot
	BHL: 1591 FNL / 606 FEL	SENE	Lot
<u>API #</u>	<u>BONANZA 1023-6H2CS</u>		
	Surface: 2192 FNL / 634 FEL	SENE	Lot
	BHL: 1806 FNL / 1020 FEL	SENE	Lot
<u>API #</u>	<u>BONANZA 1023-6I2AS</u>		
	Surface: 2192 FNL / 644 FEL	SENE	Lot
	BHL: 2622 FSL / 942 FEL	NESE	Lot

This Surface Use Plan of Operations (SUPO) or 13-point plan provides the site-specific information for the above-referenced wells. This information incorporates by reference the Master Development Plan (MDP) for Kerr-McGee Oil & Gas Onshore LP (KMG). The MDP is available upon request from the BLM-Vernal Field Office.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

An on-site meeting was held on June 16, 2010. Present were:

- Dave Gordon, Suzanne Gray and Dan Emmett – BLM;
- John Slaugh, Brock Slaugh and Mitch Batty- Timberline Engineering & Land Surveying, Inc.; and
- Roger Parry, Clay Einerson, Grizz Oleen, Sheila Wopsock, Lovell Young, Grizz Oleen, Hal Blanchard, Lance Morton, Tim Donovan, Kathie Zehren, Laura Gianakos and Charles Chase – Kerr-McGee

A. Existing Roads:

- A) Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

The following segments are "onlease", no ROW needed.

±385' (0.7 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, from the road re-route traveling west to lease boundary. Please see Topo D and Exhibit B2.

The following segments require a ROW.

- ±3,120' (0.6 miles) – Section 6 T10S R23E (SW/4 NE/4) – Lease UTU38419, from the northeastern lease line boundary to the southeast lease and section boundary in the NE/4 SE/4 of Section 6. Please refer to Exhibit B2, Lines 6 and 5.
- ±1,310' (0.3 miles) – Section 5 T10S R23E (SW/4 SW/4) – Lease UTU73450, from the western section line boundary the southern section line boundary. Please refer to Exhibit B2, Line 4.
- ±40' (0.01 miles) – Section 8 T10S R23E (NW/4 NW/4) – Lease UTU37355, dips into the northern section line boundary and back up to northern section line boundary. Please refer to Exhibit B2, Line 3.
- ±600' (0.1 miles) – Section 5 T10S R23E (SW/4 SW/4) – Lease UTU73450, comes in from the southern section boundary line, travels east, then back to the southern section boundary line. Please refer to Exhibit B2, Line 2.
- ±1,010' (0.2 miles) – Section 8 T10S R23E (NW/4 NW/4) – Lease UTU37355, enters the northern section line boundary and ties in to existing road in the NE/4 NW/4 of section 8. Please refer to Exhibit B2, Line 1.

B. New or Reconstructed Access Roads:

See MDP for additional details on road construction.

- ±100' (0.7 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, re-route 100' of new road from the edge of pad to the existing road tie-in. Please see Topo D and Exhibit B2.

C. Location of Existing Wells:

- A) Refer to Topo Map C.

D. Location of Existing and/or Proposed Facilities:

See MDP for additional details on Location of Existing and/or Proposed Facilities. Also, please refer to Exhibit B and Topo D- Pad and Pipeline Detail.

This pad will expand the existing pad for the Bonanza 1023-6H, which is a producing gas well according to Utah Division of Oil, Gas and Mining (UDOGM) records on December 29, 2010. Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee Oil and Gas Onshore LP (KMG).

GAS GATHERING

The gas gathering pipeline material: Steel line pipe with fusion bond epoxy coating. The total gas gathering pipeline distance from the meter to the tie in point is ±13,980' and the individual segments are broken up as follows:

The following segments are "onlease", no ROW needed.

- ±450' (0.09 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, BLM surface, New 6" buried gas gathering pipeline from the meter to the edge of the pad. Please refer to Topo D- Pad and Pipeline Detail.
- ±160' (0.03 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, BLM surface, New 6" buried gas gathering pipeline from the edge of the pad to the tie-in at the new 10" buried gas gathering pipeline at the 5L Intersection. Please refer to Topo D Pad and Pipeline Detail.

±340' (0.06 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, BLM surface, New 10" buried gas gathering pipeline that travel west to the lease line boundary. Please see Topo D Pad and Pipeline Detail.

The following segments require a ROW.

- ±930' (0.2 miles) – Section 6 T10S R23E (SW/4 NE/4) – Lease UTU38419, BLM surface, New 10" buried gas gathering pipeline from the northeastern lease line boundary (SW/4 NE/4) traveling in a southerly direction to the 16" buried gas gathering line tie-in (NW/4 SE/4). Please refer to Exhibit A1, Line 7.
- ±5,640' (1.1 miles) – Section 6 T10S R23E (NW/4 SE/4) – Lease UTU38419, BLM surface, New 16" buried gas gathering line from the 10" tie-in to the western section line boundary. Please see Exhibit A1, Lines 8, 9, 11, 12 and 13. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6F, Bonanza 1023-5L and Bonanza 1023-5M Pads.
- ±6,460' (1.2 miles) – Section 1 T10S R22E (NE/4 NE/4) – Lease UTU011336, BLM surface, New 16" buried gas gathering pipeline from the eastern section line boundary to the southern section line boundary. Please refer to Exhibit A1, Line 14. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6F, Bonanza 1023-5L and Bonanza 1023-5M Pads.

The remaining gas pipeline section that will go to the existing Tank Battery, will be on state surface. Kerr-McGee will apply for the appropriate state rights of way.

Kerr-McGee, additionally will install a gas gathering line in a southeasterly direction to tie into an existing buried pipeline. The total of this proposed gas gathering from the meter to the tie in point is ±6,940 and the individual segments are broken up as follows:

The following segments are "onlease", no ROW needed.

- ±450' (0.09 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, BLM surface, New 6" buried gas gathering pipeline from the meter to the edge of the pad. Please refer to Topo D-Pad and Pipeline Detail.
- ±160' (0.03 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, BLM surface, New 6" buried gas gathering pipeline from the edge of the pad to the tie-in at the new 10" buried gas gathering pipeline at the 5L Intersection. Please refer to Topo D Pad and Pipeline Detail.
- ±340' (0.06 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, BLM surface, New 10" buried gas gathering pipeline that travel west to the lease line boundary. Please see Topo D Pad and Pipeline Detail.

The following segments require a ROW.

- ±930' (0.2 miles) – Section 6 T10S R23E (SW/4 NE/4) – Lease UTU38419, BLM surface, New 10" buried gas gathering pipeline from the northeastern lease line boundary (SW/4 NE/4) traveling in a southerly direction to the 16" buried gas gathering line tie-in (NW/4 SE/4). Please refer to Exhibit A1, Line 7.
- ±2,160' (0.4 miles) – Section 6 T10S R23E (NW/4 SE/4) – Lease UTU38419, BLM surface, New 16" buried gas gathering line from the 10" tie-in to the eastern section line boundary. Please see Exhibit A1, Line 6. This portion of pipeline will be used concurrently with the Bonanza 1023-6B,

- Bonanza 1023-6C, Bonanza 1023-6F, Bonanza 1023-5L and Bonanza 1023-5M Pads.
- ±1,220' (0.2 miles) – Section 5 T10S R23E (SW/4 SW/4) – Lease UTU73450, BLM surface, New 16" gas gathering pipeline from the west lease boundary of 1023-Section 5 to the southern lease boundary of 1023-Section 5. Please refer to Exhibit A1, Line 5. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6F, Bonanza 1023-5L and Bonanza 1023-5M Pads.
- ±190' (0.03 miles) – Section 8 T10S R23E (NW/4 NW/4) – Lease UTU37355, BLM surface, New 16" gas gathering pipeline dips in from the north lease boundary of 1023-Section 8 and back north to the section boundary. Please refer to Exhibit A1, Line 4. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6F, Bonanza 1023-5L and Bonanza 1023-5M Pads.
- ±360' (0.03 miles) – Section 5 T10S R23E (SW/4 SW/4) – Lease UTU73450, BLM surface, New 16" gas gathering pipeline dips in from the south lease boundary of 1023-Section 5 and back south to the section boundary. Please refer to Exhibit A1, Line 3 and 2. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6F, Bonanza 1023-5L and Bonanza 1023-5M Pads.
- ±1,130' (0.2 miles) – Section 8 T10S R23E (NW/4 NW/4) – Lease UTU37355, BLM surface, New 16" gas gathering pipeline comes in from the north lease boundary of 1023-Section 8 and goes southeasterly to the tie in point in the NENW of 1023 section 8. Please refer to Exhibit A1, Line 1. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6F, Bonanza 1023-5L and Bonanza 1023-5M Pads.

Kerr-McGee will transport fluids (Gas and Liquids) via either or both of the said pipelines.

LIQUID GATHERING

The total liquid gathering pipeline distance from the separator to the tie in point is ±13,980' and the individual segments are broken up as follows:

The following segments are "onlease", no ROW needed.

- ±450' (0.09 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, BLM surface, New 6" buried liquid gathering pipeline from the separator to the edge of the pad. Please refer to Topo D Pad and Pipeline Detail.
- ±500' (0.09 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, BLM surface, New 6" buried liquid gathering pipeline from the edge of the pad to to the western lease line boundary. Please refer Exhibit B, Lines 7 and 4.

The following segments require a ROW.

- ±6,570' (1.2 miles) – Section 6 T10S R23E (SW/4 NE/4) – Lease UTU38419, BLM surface, New 6" buried liquid gathering pipeline from the eastern lease line boundary to the western section line boundary. Please refer to Exhibit B1, Lines 6, 19, 18, 2, 3 and 4. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6F, Bonanza 1023-5L and Bonanza 1023-5M Pads.

±6,460' (1.2 miles) – Section 1 T10S R22E (NE/4 NE/4) – Lease UTU011336, BLM surface, New 6" buried liquid gathering pipeline from the eastern section line boundary to the southern section line boundary. Please refer to Exhibit B1, Line 5. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6F, Bonanza 1023-5L and Bonanza 1023-5M Pads.

The remaining liquid pipeline section that will go to the existing Tank Battery, will be on state surface. Kerr-McGee will apply for the appropriate state rights of way.

Kerr-McGee, additionally will install a liquid gathering line in a southeasterly direction to tie into an existing buried pipeline. The total of this proposed liquid gathering from the separator to the tie in point is ±6,940 and the individual segments are broken up as follows:

The following segments are "onlease", no ROW needed.

- ±450' (0.09 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, BLM surface, New 6" buried liquid gathering pipeline from the separator to the edge of the pad. Please refer to Topo D Pad and Pipeline Detail.
- ±500' (0.09 miles) – Section 6 T10S R23E (SE/4 NE/4) – On-lease UTU33433, BLM surface, New 6" buried liquid gathering pipeline from the edge of the pad to to the western lease line boundary. Please refer Exhibit B, Lines 7 and 4.

The following segments require a ROW.

- ±3,090' (0.6 miles) – Section 6 T10S R23E (SW/4 NE/4) – Lease UTU38419, BLM surface, New 6" buried liquid gathering pipeline from the eastern lease line boundary to the eastern section line boundary. Please refer to Exhibit A1, Lines 7 and 6. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6F, Bonanza 1023-5L and Bonanza 1023-5M Pads.
- ±1,220' (0.2 miles) – Section 5 T10S R23E (SW/4 SW/4) – Lease UTU73450, BLM surface, New 6" liquid gathering pipeline from the west lease boundary of 1023-Section 5 to the southern lease boundary of 1023-Section 5. Please refer to Exhibit B1, Line 8. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6H, Bonanza 1023-5L and Bonanza 1023-5M Pads.
- ±190' (0.03 miles) – Section 8 T10S R23E (NW/4 NW/4) – Lease UTU37355, BLM surface, New 6" liquid gathering pipeline dips in from the north lease boundary of 1023-Section 8 and back north to the section boundary. Please refer to Exhibit B1, Line 9. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6H, Bonanza 1023-5L and Bonanza 1023-5M Pads.
- ±360' (0.03 miles) – Section 5 T10S R23E (SW/4 SW/4) – Lease UTU73450, BLM surface, New 6" liquid gathering pipeline dips in from the south lease boundary of 1023-Section 5 and back south to the section boundary. Please refer to Exhibit B1, Line 10 and 16. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6H, Bonanza 1023-5L and Bonanza 1023-5M Pads.
- ±1,130' (0.2 miles) – Section 8 T10S R23E (NW/4 NW/4) – Lease UTU37355, BLM surface, New 6" gas gathering pipeline comes in from the north lease boundary of 1023-Section 8 and goes southeasterly to the tie in point in the NENW of 1023 section 8. Please refer to Exhibit B1, Line 17. This portion of pipeline will be used concurrently with the Bonanza 1023-6B, Bonanza 1023-6C, Bonanza 1023-6H, Bonanza 1023-5L and Bonanza 1023-5M Pads.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

The proposed buried pipelines will be constructed utilizing existing disturbance when possible. The area of disturbance during construction from the edge of road or well pad will be 30' in width. The total pipeline disturbance width will be 30'. Where possible there will be no additional disturbance during construction, as the road will be utilized for construction vehicles. The liquid and gas gathering lines will be in the same trench.

The proposed trench width for the pipeline would range from 18-48 inch and will be excavated to a depth of 48 to 60 inches of normal soil cover or 24 inches of cover in consolidated rock. The pipeline will be welded or zap locked along the proposed right-of-way and lowered into place. During construction blasting may occur along the proposed right-of-way when trenching equipment can not cut into the bedrock. Large debris and rocks removed from the earth during trenching and blasting that could not be returned to the trench would be distributed evenly and naturally in the project area. The proposed buried pipeline will be visually and radiographically inspected and the entire pipeline will be pneumatically tested before being placed into service.

Upon completion of the proposed buried pipeline, the entire area of disturbance will be reclaimed to the standards proposed in the Green River District Reclamation Guidelines. Please refer to the MDP for more details regarding final reclamation. Pipeline signs will be installed along the right-of-way to indicate the pipeline proximity, ownership, and to provide emergency contact phone numbers. Above ground valves and lateral T's will be installed at various locations to connect the new line to existing facilities and/or for safety purposes. Kerr-McGee requests for a permanent 30' right-of-way that will be maintained for the portion adjacent to the road. The need for the 30' permanent right-of-way is for maintenance and repairs.

When no longer serving a useful purpose, Kerr-McGee or it's successor will consult with the BLM, Vernal Field Office before termination.

The Anadarko Completions Transportation System (ACTS) information:

See MDP for additional details on the ACTS System.

Upon completion of the wells on this pad, Kerr-McGee is also requesting to utilize this pit as an Anadarko Completion Transport System (ACTS) staging pit which will be utilized for other completion operations in the area. The ACTS process will reduce the amount of truck traffic on a field-wide basis, also reducing vehicle emissions and fugitive dust generation.

Kerr-McGee will use ACTS to optimize the completion processes for multiple pads across the project area which may include up to a section of development. ACTS will facilitate management of frac fluids by utilizing existing reserve pits and temporary, surface-laid aluminum liquids transfer lines between frac locations. The refurbished pit will be relined per the guidelines in the MDP. The pit will be refurbished as follows: mix and pile up drill cuttings with dry dirt, bury the original liner in the pit, walk bottom of pit with cat. Kerr-McGee will reline the pit with a 30 mil liner and double felt padding. The refurbished pit will be the same size or smaller as specified in the originally approved ROW/APD. The pit refurb will be done in a normal procedure and there will be no modification to the pit that does not coincide with Kerr-McGee's MDP. Hog fence panels (5' X 16') will be built and painted shadow gray and will be put up on the work side of the pit. Polypropylene netting will be installed over all pits. There will be two 500 bbl temporary frac tanks placed on the location. The trucks will unload water into these tanks before the water is placed into the refurbished pit. The

purpose of the temporary frac tanks is to collect any hydro-carbons that may have been associated with the other completion operations before releasing into the pit. The collected hydrocarbons will be treated and sold at approved sales facilities. A loading rack with drip containment will be also be installed where water trucks would unload and load to prevent damage caused from pulling hoses in and out of the pit .

ACTS will require temporarily laying multiple 6" aluminum water transfer lines on the surface between either existing or refurbished reserve pits. Please see the attached ACTS exhibit C for placement of the proposed temporary lines. The temporary aluminum transfer lines will be utilized to transport frac fluid being injected and/or recovered during the completion process and will be laid adjacent to existing access roads. Upon completion of the frac operation, the liquids transfer lines will be flushed with fresh water and purged with compressed air. The contents of the transfer lines will be flushed into a water truck for delivery to another ACTS location or a reserve pit.

The volume of frac fluid transported through a water transfer line will vary, but volume is projected to be approximately 1.75 bbls per 50-foot joint. Although the maximum working pressure is 125 psig, the liquids transfer lines will be operated at a pressure of approximately 30 to 40 psig.

Kerr-McGee requests to keep this netted pit open for one year. During this time the surrounding well location completion fluids may be recycled in this pit and utilized for other frac jobs in the area. After one year Kerr-McGee will backfill the pit and reclaim as stated in the MDP. Kerr-McGee understands that due to the temporary nature of this system, BLM considers this a casual use situation; therefore, no permanent ROW or temporary use plan will need to be issued by the BLM.

E. Location and Types of Water Supply:

See MDP for additional details on Location and Type of Water Supply.

Water for drilling and completion operations will be obtained from the following sources:

Permit # 49-2307	JD Field Services	Green River- Section 15, T2N, R22E
Permit # 49-2321	R.N. Industries	White River- Section 2, T10S, R24E
Permit # 49-2319	R.N. Industries	White River- Various Sources
Permit # 49-2320	R.N. Industries	Green River- Section 33, T8S, R23E

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

F. Construction Materials:

See MDP for additional details on Source of Construction Materials.

G. Methods for Handling Waste:

See MDP for additional details on Methods of Handling Waste Materials

Fluids disposal and pipeline/haul routes are depicted on Topo Map A.

Any produced water separated from recoverable condensate from the proposed well will be contained in a water tank and will then be transported by pipeline and/or truck to one of the pre-approved disposal sites:

Bonanza 1023-6A3DS/ 1023-6G1DS/ 1023-6H1BS/ 1023-6H2CS/
1023-6I2AS
Kerr-McGee Oil Gas Onshore, L.P.

Bonanza 1023-6H Pad
Surface Use Plan of Operations
8 of 10

RNI in Sec. 5 T9S R22E
NBU #159 in Sec. 35 T9S R21E
Ace Oilfield in Sec. 2 T6S R20E
MC&MC in Sec. 12 T6S R19E
Pipeline Facility in Sec. 36 T9S R20E
Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E
Bonanza Evaporation Pond in Sec. 2 T10S R23E

Or to one of the following Kerr-McGee active Salt Water Disposal (SWD) wells:

NBU 159 SWD in Sec. 35 T9S R21E
CIGE 112D SWD in Sec. 19 T9S R21E
CIGE 114 SWD in Sec. 34 T9S R21E
NBU 921-34K SWD in Sec. 34 T9S R21E
NBU 921-33F SWD in Sec. 34 T9S R21E

H. Ancillary Facilities:

See MDP for additional details on Ancillary Facilities.
None are anticipated.

I. Well Site Layout:

See MDP and Well Pad Design Summary for additional details on Well Site Layout.

J. Plans for Surface Reclamation:

See MDP for additional details on Plans for Reclamation of the Surface.

Site Specific Reclamation Considerations:

Reclamation Monitoring Reference Point for all wells on Pad (where a reclamation monitoring point has not been established at the time of APD submission, it will be submitted for approval under separate cover prior to surface disturbing activities):

Seed Mix to be used for Well Site, Access Road, and Pipeline (as applicable):

Bonanza Area Mix	Pure Live Seed lbs/acre
Crested Wheat (Hycrest)	2
Bottlebrush Squirreltail	1
Western Wheatgrass (Arriba)	1
Indian Ricegrass	1
Fourwing Saltbush	2
Shadscale	2
Forage Kochia	0.25
Rocky Mountain Bee Plant	0.5
Total	9.75

Bonanza 1023-6A3DS/ 1023-6G1DS/ 1023-6H1BS/ 1023-6H2CS/
1023-6I2AS
Kerr-McGee Oil Gas Onshore, L.P.

Bonanza 1023-6H Pad
Surface Use Plan of Operations
9 of 10

K. Surface/Mineral Ownership:

United States of America
Bureau of Land Management
170 South 500 East
Vernal, UT 84078
(435)781-4400

L. Other Information:

See MDP for additional details on Other Information.

Onsite Specifics:

- Construction: 30 Mil Double Felt
- Construction: Need to reclaim the old access road when new road is built. Add ditch & culvert at the access road
- Facilities: Will be painted Shadow Grey
- Top Soil: Existing top soil to stay north of the location

Resource Reports:

A Class I literature survey was completed on August 20, 2010 by Montgomery Archaeological Consultants, Inc (MOAC). For additional details please refer to report MOAC 10-066b.

A paleontological reconnaissance survey was completed on May 13, 2010 by SWCA Environmental Consultants. For additional details please refer to report UT10-14314-27.

Biological field survey was completed on May 11, 2010 by Grasslands Consulting, Inc (GCI). For additional details please refer to report GCI-217.

Right-of-Ways (ROW):

See MDP for additional information on ROW

M. Lessee's or Operators' Representative & Certification:

Gina T. Becker
Regulatory Analyst II
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6086

Tommy Thompson
General Manager, Drilling
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.


Gina T. Becker

December 29, 2010
Date

API Number: 4304751459

Well Name: BONANZA 1023-6A3DS




Township 10.0 S Range 23.0 E Section 06

Meridian: SLBM

Operator: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Map Prepared:

Map Produced by Diana Mason



WORKSHEET

APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 1/4/2011

API NO. ASSIGNED: 43047514590000

WELL NAME: BONANZA 1023-6A3DS

OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995)

PHONE NUMBER: 720 929-6086

CONTACT: Gina Becker

PROPOSED LOCATION: SENE 06 100S 230E

Permit Tech Review: ☒

SURFACE: 2191 FNL 0624 FEL

Engineering Review: ☒

BOTTOM: 1095 FNL 0800 FEL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 39.97931

LONGITUDE: -109.36178

UTM SURF EASTINGS: 639887.00

NORTHINGS: 4426536.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU33433

PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

SURFACE OWNER: 1 - Federal

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- ☒ PLAT
- ☒ Bond: FEDERAL - WYB000291
- ☐ Potash
- ☐ Oil Shale 190-5
- ☐ Oil Shale 190-3
- ☐ Oil Shale 190-13
- ☒ Water Permit: Permit #43-8496
- ☐ RDCC Review:
- ☐ Fee Surface Agreement
- ☒ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

- ☐ R649-2-3.
- Unit:
- ☐ R649-3-2. General
- ☐ R649-3-3. Exception
- ☒ Drilling Unit
- Board Cause No: Cause 179-14
- Effective Date: 6/12/2008
- Siting: 460' Fr Exterior Drilling Unit Boundary
- ☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations:
3 - Commingle - ddoucet
4 - Federal Approval - dmason
15 - Directional - dmason



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: BONANZA 1023-6A3DS

API Well Number: 43047514590000

Lease Number: UTU33433

Surface Owner: FEDERAL

Approval Date: 1/19/2011

Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 179-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Commingling:

In accordance with Board Cause No. 179-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)
OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <https://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

JAN 05 2011
2011

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU33433	
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name	
2. Name of Operator KERR-MCGEE OIL & GAS ONSHORE		7. If Unit or CA Agreement, Name and No. CA-60768 CR-3	
Contact: GINA T BECKER Email: GINA.BECKER@ANADARKO.COM		8. Lease Name and Well No. BONANZA 1023-6A3DS	
3a. Address P.O. BOX 173779 DENVER, CO 80202-3779		9. API Well No. 43-047-51459	
3b. Phone No. (include area code) Ph: 720-929-6086 Fx: 720-929-7086		10. Field and Pool, or Exploratory BONANZA	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SENE 2191FNL 624FEL 39.97923 N Lat, 109.36235 W Lon At proposed prod. zone NENE Lot 1 1095FNL 800FEL 39.98224 N Lat, 109.36298 W Lon		11. Sec., T., R., M., or Blk. and Survey or Area Sec 6 T10S R23E Mer SLB	
14. Distance in miles and direction from nearest town or post office* APPROXIMATELY 47.5 MILES SOUTH OF VERNAL, UTAH		12. County or Parish UINTAH	
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 800		13. State UT	
16. No. of Acres in Lease 1923.00		17. Spacing Unit dedicated to this well	
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 770		20. BLM/BIA Bond No. on file WYB000291	
21. Elevations (Show whether DF, KB, RT, GL, etc.) 5208 GL		23. Estimated duration 60-90 DAYS	
22. Approximate date work will start 06/30/2011			

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) GINA T BECKER Ph: 720-929-6086	Date 01/04/2011
Title REGULATORY ANALYST II		
Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date AUG 17 2011
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #99953 verified by the BLM Well Information System
For KERR-MCGEE OIL & GAS ONSHORE, sent to the Vernal
Committed to AFMSS for processing by ROBIN R. HANSEN on 01/06/2011 ()

RECEIVED

AUG 29 2011

DIV. OF OIL, GAS & MINING

UDOGM

NOTICE OF APPROVAL

CONDITIONS OF APPROVAL ATTACHED

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

IDRRH0291AE

NOS 4/26/2010



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Kerr McGee Oil & Gas Onshore
Well No: Bonanza 1023-6A3DS
API No: 43-047-51459

Location: SENE, Sec. 6, T10S, R23E
Lease No: UTU-33433
Agreement: CA-60768 CR-3

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

- | | |
|---|--|
| Location Construction
(Notify Environmental Scientist) | - Forty-Eight (48) hours prior to construction of location and access roads. |
| Location Completion
(Notify Environmental Scientist) | - Prior to moving on the drilling rig. |
| Spud Notice
(Notify Petroleum Engineer) | - Twenty-Four (24) hours prior to spudding the well. |
| Casing String & Cementing
(Notify Supv. Petroleum Tech.) | - Twenty-Four (24) hours prior to running casing and cementing all casing strings to: ut_vn_opreport@blm.gov . |
| BOP & Related Equipment Tests
(Notify Supv. Petroleum Tech.) | - Twenty-Four (24) hours prior to initiating pressure tests. |
| First Production Notice
(Notify Petroleum Engineer) | - Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days. |

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

Site Specific Conditions of Approval

- One site, 42UN3526, an Archaic lithic scatter was identified near the proposed pipeline. It has been recommended as "eligible" to the NRHP. MOAC recommends temporary fence should be erected prior to construction of the pipeline to facilitate avoidance of this site and no cultural monitoring. However, the BLM is requiring no fence and a qualified archaeologist must be present for monitoring during all construction activities in the area of the eligible site.
- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horse power must not emit more than 2 grams of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower-hour.
- All vehicles and equipment shall be cleaned either through power-washing, or other approved method, if the vehicles or equipment were previously operated outside the Uinta Basin, to prevent weed seed introduction.
- All disturbance areas shall be monitored for noxious weeds annually, for a minimum of three growing seasons following completion of project or until desirable vegetation is established
- Noxious and invasive weeds will be controlled throughout the area of project disturbance.
- Noxious weeds will be inventoried and reported to BLM in the annual reclamation report. Where an integrated pest management program is applicable, coordination has been undertaken with the state and local management program (if existing). A copy of the pest management plan will be submitted for each project.
- A pesticide use permit (PUP) will be obtained for the project, if applicable.
- Kerr McGee will adhere to all applicant committed conservation measures and conservation recommendations that are stated in the USFWS's "Final Biological Opinion for the Anadarko Petroleum Corporation Natural Buttes Unit and Bonanza Area Natural Gas Development Project."
- The operator will follow the Green River District Reclamation Guidelines for reclamation.

- A permitted paleontologist is to be present to monitor construction during all surface disturbing activities: examples include the following building of the well pad, access road, and pipelines.

The following measures are required by and have been committed to by Anadarko within the Programmatic Section 7 consultation for the Natural Buttes Unit and Bonanza Area Natural Gas Development for all areas where surface disturbing activities cannot be avoided by the required 300 foot buffer from identified Uinta Basin hookless cactus individuals

- Silt fencing will be used to protect populations within 300 feet of surface disturbing activities that are downslope or downwind of the surface disturbance
- A qualified botanist will be on site to monitor the surface-disturbing activities.
- Dust abatement will occur and will be done using only water.
- All cacti within 300 feet will be flagged immediately prior to surface-disturbing activities are completed.
- Pipelines will be located to the far side of the Right-of-Way to maximize distance from cacti.
- Project personnel associated with construction activities would be instructed to drive at a speed limit of 15 miles per hour on unpaved roads and to remain on the existing roads and approved Rights-of-Way at all times.

Discovery Stipulation: Reinitiation of section 7 consultation with the USFWS will be sought immediately if any loss of plants or occupied habitat for Pariette cactus or Uinta Basin hookless cactus is anticipated as a result of project activities.

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

- Gamma Ray Log shall be run from Total Depth to Surface.
- Cement for the production casing shall be brought 200 feet above the surface casing shoe.

Variances Granted:

Air Drilling

- Approved - Variance requested for Air Drill BOPE
- Approved - Variance requested for mud materials
- Approved - Variance requested for FIT.
- Approved - Variance requested for blooie line to be 50' minimum.
- Approved - Variance requested for requirement for automatic igniter or continuous pilot light on the blooie line.
- Approved - Variance requested to allow for rig mounted air compressors 40' from the wellbore.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order

No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's

log.

- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid,

and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU33433
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-6A3DS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2191 FNL 0624 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 06 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047514590000
PHONE NUMBER: 720 929-6515 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 10/7/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The Operator requests approval for changes in the drilling program. This request includes options for the use of a Closed Loop system, and change in casing design. Please see attachment for details. Please contact the undersigned if you have any questions and/or concerns.		
Accepted by the Utah Division of Oil, Gas and Mining Date: 10/12/2011 By:		
NAME (PLEASE PRINT) Andy Lytle		PHONE NUMBER 720 929-6100
TITLE Regulatory Analyst		DATE 10/6/2011
SIGNATURE N/A		

BONANZA 1023-6H PAD

Drilling Program
1 of 7**Kerr-McGee Oil & Gas Onshore. L.P.****BONANZA 1023-6A3DS**

Surface: 2191 FNL / 624 FEL SENE
 BHL: 1095 FNL / 800 FEL SWNENE

Section 6 T10S R23E

Uintah County, Utah
 Mineral Lease: UTU-33433

ONSHORE ORDER NO. 1**DRILLING PROGRAM**

1. & 2. **Estimated Tops of Important Geologic Markers:**
Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1248	
Birds Nest	1522	Water
Mahogany	1882	Water
Wasatch	4272	Gas
Mesaverde	6388	Gas
MVU2	7367	Gas
MVL1	7929	Gas
TVD	8550	
TD	8725	

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Drilling Program

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

6. **Evaluation Program:**

Please refer to the attached Drilling Program

7. Abnormal Conditions:

Maximum anticipated bottom hole pressure calculated at 8550' TVD, approximately equals
5,472 psi (0.64 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,579 psi (bottom hole pressure
minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-
(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. Variances:

Please refer to the attached Drilling Program.

Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


10. Other Information:

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP					DATE	October 6, 2011		
WELL NAME	BONANZA 1023-6A3DS					TD	8,550'	TVD	8,725' MD
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah	FINISHED ELEVATION		5,207'
SURFACE LOCATION	SENE	2191 FNL	624 FEL	Sec 6	T 10S	R 23E			
	Latitude: 39.979229		Longitude: -109.362350			NAD 83			
BTM HOLE LOCATION	SWNE	1095 FNL	800 FEL	Sec 6	T 10S	R 23E			
	Latitude: 39.982236		Longitude: -109.362980			NAD 83			
OBJECTIVE ZONE(S)	Wasatch/Mesaverde								
ADDITIONAL INFO	Regulatory Agencies: BLM (Minerals), BLM (Surface), UDOGM Tri-County Health Dept.								





KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS			
						LTC		DQX	
						BURST	COLLAPSE	TENSION	
CONDUCTOR	14"	0-40'							
						3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0 to 2,330	28.00	IJ-55	LTC	2.32	1.72	6.09	N/A
						7,780	6,350	223,000	267,000
PRODUCTION	4-1/2"	0 to 5,000	11.60	I-80	DQX	1.11	1.14		3.26
	4-1/2"	5,000 to 8,725'	11.60	I-80	LTC	1.11	1.14	6.38	

Surface Casing:

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoys.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoys.Fact. of water)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl + 0.25 pps flocele	180	60%	15.80	1.15
Option 1							
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt + 2% CaCl + 0.25 pps flocele	270	0%	15.80	1.15
SURFACE			NOTE: If well will circulate water to surface, option 2 will be utilized				
Option 2	LEAD	1,830'	65/35 Poz + 6% Gel + 10 pps gilsonite + 0.25 pps Flocele + 3% salt BWOW	170	35%	11.00	3.82
	TAIL	500'	Premium cmt + 2% CaCl + 0.25 pps flocele	150	35%	15.80	1.15
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	3,765'	Premium Lite II +0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	280	20%	11.00	3.38
	TAIL	4,960'	50/50 Poz/G + 10% salt + 2% gel + 0.1% R-3	1,170	35%	14.30	1.31

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Nick Spence / Danny Showers / Chad Loesel


DATE:

DRILLING SUPERINTENDENT:

Kenny Gathings / Lovel Young

DATE:

EXHIBIT A BONANZA 1023-6A3DS



Requested Drilling Options:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one cuttings storage area to be constructed on the drilling pad or a traditional drilling operation with one pit used for drilling and completion operations. The cuttings storage area will be used to contain only the de-watered drill cuttings and will be lined and bermed to prevent any liquid runoff. The drill cuttings will be buried in the completion pit once completion operations are completed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit will be lined with a synthetic material 20 mil or thicker and will be used for the completing of the wells on the pad or used as part of our Aandarko Completions Transportation System (ACTS). Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completions pit.

If Kerr-McGee does not use a closed loop drilling system, it will construct a traditional drilling/completions pit to contain drill cuttings and for use in completion operations. The pit will be lined with a synthetic material 20 mil or thicker. The drill cuttings will be buried in the pit using traditional pit closure standards.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU33433
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-6A3DS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2191 FNL 0624 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 06 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047514590000
9. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH
STATE: UTAH		
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 11/8/2011	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 CONDUCTOR PIPE. CMT W/ 28 SX READY MIX. SPUD WELL LOCATION ON NOVEMBER 8, 2011 AT 12:00 HRS.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 11/10/2011	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU33433			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-6A3DS			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2191 FNL 0624 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 06 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047514590000			
10. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		STATE: UTAH			
TYPE OF SUBMISSION <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 11/8/2011 <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 CONDUCTOR PIPE. CMT W/ 28 SX READY MIX. SPUD WELL LOCATION ON NOVEMBER 8, 2011 AT 12:00 HRS.					
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY					
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regulatory Analyst			
SIGNATURE N/A	DATE 11/10/2011				

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company KERR-McGEE OIL & GAS ONSHORE, L.P.

Well Name: BONANZA 1023-6A3DS

Api No: 43-047-51459 Lease Type FEDERAL

Section 06 Township 10S Range 23E County UINTAH

Drilling Contractor PETE MARTIN DRLG RIG # BUCKET

SPUDDED:

Date 11/08/2011

Time 10:00 AM

How DRY

**Drilling will
Commence:** _____

Reported by SHEILA WOPSOCK

Telephone # (435) 781-7024

Date 11/08/2011 Signed CHD

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company KERR-McGEE OIL & GAS ONSHORE, L.P.

Well Name: BONANZA 1023-6A3DS

Api No: 43-047-51459 Lease Type FEDERAL

Section 06 Township 10S Range 23E County UINTAH

Drilling Contractor PETE MARTIN DRLG RIG # BUCKET

SPUDDED:

Date 11/08/2011

Time 10:00 AM

How DRY

**Drilling will
Commence:**

Reported by SHEILA WOPSOCK

Telephone # (435) 781-7024

Date 11/08/2011 Signed CHD

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR MCGEE OIL & GAS ONSHORE LP
Address: P.O. Box 173779
city DENVER
state CO zip 80217

Operator Account Number: N 2995
Phone Number: (720) 929-6100

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304751461	BONANZA 1023-6H1BS		SENE	6	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	18302	11/8/2011		11/16/11		
Comments: MIRU PETE MARTIN BUCKET RIG. <i>WSMVD</i> SPUD WELL LOCATION ON 11/08/2011 AT 07:30 HRS. <i>BHL = SENE</i>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304751459	BONANZA 1023-6A3DS		SENE	6	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	18303	11/8/2011		11/16/11		
Comments: MIRU PETE MARTIN BUCKET RIG. <i>WSMVD</i> SPUD WELL LOCATION ON 11/08/2011 AT 12:00 HRS. <i>BHL = NENE</i>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304751462	BONANZA 1023-6H2CS		SENE	6	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	18304	11/8/2011		11/16/11		
Comments: MIRU PETE MARTIN BUCKET RIG. <i>WSMVD</i> SPUD WELL LOCATION ON 11/08/2011 AT 18:00 HRS. <i>BHL = SENE</i>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

JAIME SCHARNOWSKE

Name (Please Print)

Jaime Scharnowske

Signature

REGULATORY ANALYST

11/10/2011

Title

Date

RECEIVED

NOV 14 2011

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9																														
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU33433																														
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:																														
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:																														
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-6A3DS																														
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2191 FNL 0624 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 06 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047514590000																														
10. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH																														
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		STATE: UTAH																														
TYPE OF SUBMISSION <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 11/22/2011	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td><input type="checkbox"/> ACIDIZE</td> <td><input type="checkbox"/> ALTER CASING</td> <td><input type="checkbox"/> CASING REPAIR</td> </tr> <tr> <td><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</td> <td><input type="checkbox"/> CHANGE TUBING</td> <td><input type="checkbox"/> CHANGE WELL NAME</td> </tr> <tr> <td><input type="checkbox"/> CHANGE WELL STATUS</td> <td><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</td> <td><input type="checkbox"/> CONVERT WELL TYPE</td> </tr> <tr> <td><input type="checkbox"/> DEEPEN</td> <td><input type="checkbox"/> FRACTURE TREAT</td> <td><input type="checkbox"/> NEW CONSTRUCTION</td> </tr> <tr> <td><input type="checkbox"/> OPERATOR CHANGE</td> <td><input type="checkbox"/> PLUG AND ABANDON</td> <td><input type="checkbox"/> PLUG BACK</td> </tr> <tr> <td><input type="checkbox"/> PRODUCTION START OR RESUME</td> <td><input type="checkbox"/> RECLAMATION OF WELL SITE</td> <td><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</td> </tr> <tr> <td><input type="checkbox"/> REPERFORATE CURRENT FORMATION</td> <td><input type="checkbox"/> SIDETRACK TO REPAIR WELL</td> <td><input type="checkbox"/> TEMPORARY ABANDON</td> </tr> <tr> <td><input type="checkbox"/> TUBING REPAIR</td> <td><input type="checkbox"/> VENT OR FLARE</td> <td><input type="checkbox"/> WATER DISPOSAL</td> </tr> <tr> <td><input type="checkbox"/> WATER SHUTOFF</td> <td><input type="checkbox"/> SI TA STATUS EXTENSION</td> <td><input type="checkbox"/> APD EXTENSION</td> </tr> <tr> <td><input type="checkbox"/> WILDCAT WELL DETERMINATION</td> <td><input type="checkbox"/> OTHER</td> <td>OTHER: <input style="width: 100px;" type="text"/></td> </tr> </table>		<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR																														
<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME																														
<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE																														
<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION																														
<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK																														
<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION																														
<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON																														
<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL																														
<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION																														
<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>																														
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU AIR RIG ON NOV 20, 2011. DRILLED SURFACE HOLE TO 2430'. RAN SURFACE CASING AND CEMENTED. WELL IS WAITING ON ROTARY RIG. DETAILS OF CEMENT JOB WILL BE INCLUDED WITH WELL COMPLETION REPORT.																																
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY																																
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regulatory Analyst																														
SIGNATURE N/A	DATE 11/23/2011																															

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU33433
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-6A3DS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2191 FNL 0624 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 06 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047514590000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 1/14/2012	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU ROTARY RIG. FINISHED DRILLING FROM 2430' TO 8760' ON JAN. 10, 2012. RAN 4-1/2" 11.6# I-80 PRODUCTION CASING. CEMENTED PRODUCTION CASING. RELEASED XTREME RIG 12 ON JAN. 14, 2012 @ 15:00 HRS. DETAILS OF CEMENT JOB WILL BE INCLUDED WITH THE WELL COMPLETION REPORT. WELL IS WAITING ON FINAL COMPLETION ACTIVITIES.		
NAME (PLEASE PRINT) Jaime Scharnowske		PHONE NUMBER 720 929-6304
SIGNATURE N/A		TITLE Regularatory Analyst
DATE 1/17/2012		<div style="text-align: right;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY January 17, 2012 </div>

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU33433
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-6A3DS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2191 FNL 0624 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 06 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047514590000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 3/19/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. THE SUBJECT WELL WAS PLACED ON PRODUCTION ON MARCH 19, 2012 AT 4:00 P.M. THE CHRONOLOGICAL WELL HISTORY WILL BE SUBMITTED WITH THE WELL COMPLETION REPORT.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 04, 2012		
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regularatory Analyst
SIGNATURE N/A	DATE 4/2/2012	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other			5. Lease Serial No. UTU33433		
b. Type of Completion <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr. Other _____			6. If Indian, Allottee or Tribe Name		
2. Name of Operator KERR MCGEE OIL & GAS ONSHORE-Mail: cara.mahler@anadarko.com			7. Unit or CA Agreement Name and No. CA60768 CR3		
3. Address 1099 18TH STREET, SUITE 1800 DENVER, CO 80202			8. Lease Name and Well No. BONANZA 1023-6A3DS		
3a. Phone No. (include area code) Ph: 720-929-6029			9. API Well No. 43-047-51459		
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface SENE 2191FNL 624FEL 39.979229 N Lat, 109.362351 W Lon At top prod interval reported below NENE 1151FNL 799FEL At total depth NENE Lot 1 1087FNL 789FEL <i>BHL by HSM</i>			10. Field and Pool, or Exploratory NATURAL BUTTES		
14. Date Spudded 11/08/2011			11. Sec., T., R., M., or Block and Survey or Area Sec 6 T10S R23E Mer SLB		
15. Date T.D. Reached 01/10/2012			12. County or Parish UINTAH		
16. Date Completed <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod. 03/19/2012			13. State UT		
17. Elevations (DF, KB, RT, GL)* 5207 GL					
18. Total Depth: MD 8760 TVD 8617		19. Plug Back T.D.: MD 8706 TVD 8563		20. Depth Bridge Plug Set: MD TVD	
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) SD/DSN/ACTR-BHV-CBL/CML/GR/CCL			22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit analysis)		

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
20.000	14.000 STL	36.7	0	40		28			
11.000	8.625 IJ-55	28.0	0	2412		525		0	
7.875	4.500 I-80	11.6	0	8750		1734		1800	

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	8190							

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) WASATCH	5502	6418	5502 TO 6418	0.360	48	OPEN
B) MESAVERDE	7202	8635	7202 TO 8635	0.360	144	OPEN
C)						
D)						

26. Perforation Record

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
5502 TO 8635	8728 BBLs SLICK H2O & 195,240 LBS 30/50 OTTAWA SAND

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
03/19/2012	03/22/2012	24	→	0.0	2384.0	693.0			FLows FROM WELL
Choke Size	Tbg. Press. Flwg.	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
20/64	2450 SI	2313.0	→	0	2384	693		PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg.	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
	SI		→						

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #137593 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

DIV. OF OIL, GAS & MINING

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****

RECEIVED

MAY 15 2012

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

29. Disposition of Gas(Sold, used for fuel, vented, etc.)
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top Meas. Depth
				GREEN RIVER BIRD'S NEST MAHOGANY WASATCH MESAVERDE	1163 1469 2022 4407 6586

32. Additional remarks (include plugging procedure):

The first 210' of the surface hole was drilled with a 12 ?? bit. The remainder of surface hole was drilled with an 11? bit. DQX csg was run from surface to 5054?; LTC csg was run from 5054? to 8750?. Attached is the chronological well history, perforation report & final survey.

33. Circle enclosed attachments:

- | | | | |
|---|--------------------|---------------|-----------------------|
| 1. Electrical/Mechanical Logs (1 full set req'd.) | 2. Geologic Report | 3. DST Report | 4. Directional Survey |
| 5. Sundry Notice for plugging and cement verification | 6. Core Analysis | 7. Other: | |

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

Electronic Submission #137593 Verified by the BLM Well Information System.
For KERR MCGEE OIL & GAS ONSHORE L, sent to the Vernal

Name (please print) CARA MAHLER Title AUTHORIZED REPRESENTATIVE

Signature (Electronic Submission) Date 05/10/2012

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ****

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: PROPETRO 12/12, XTC 12/12

Event: DRILLING

Start Date: 10/19/2011

End Date: 1/14/2012

Active Datum: RKB @5,222.00usft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
11/20/2011	10:00 - 12:30	2.50	MIRU	01	C	P		SKID RIG 10' TO BONANZA 1023-6A3DS (WELL 2 OF 5). INSTALL DIVERTOR HEAD AND BOWIE LINE. BUILD DITCH. SPOT IN RIG. SPOT IN CATWALK AND PIPE RACKS. READY. RIG UP PIT PUMP. RIG UP PUMP. PRIME PUMP. INSPECT RIG.
	12:30 - 13:00	0.50	PRSPD	01	B	P		HELD PRE-SPUD SAFETY MEETING. TALKED ABOUT COLD WEATHER. P/U 8" 1.83 BEND .17 RPG MUD MOTOR (4TH RUN) (SN 775-77194). M/U QD507 12.25" BIT (4TH RUN) (SN 7014657). TRIP IN TO SPUD.
	13:00 - 14:30	1.50	DRLSUR	02	D	P		SPUD 11/20/2011 13:00. DRILL 12.25" HOLE 44'-210' (166', 83'/HR). GPM 400. DH RPM 68 RPM=45, WOB 5-15K. PSI ON/OFF 600/400. UP/DOWN/ ROT 20/20/20 K. DRAG 0 K. CIRC RESERVE W. 8.3# WATER. DRILL DOWN TO 210' W/ 6" COLLARS.
	14:30 - 16:30	2.00	DRLSUR	06	A	P		TRIP OUT. LAY DOWN 6" DRILL COLLARS, 12 1/4 BIT. CHECK BIT AND MOTOR. PICK UP Q508 11" BIT (2ND RUN) (SN 7019741) SCRIBE MOTOR. P/U 8" DIRECTIONAL ASSEMBLY AND SCRIBE. INSTALL EM TOOL. TRIP IN TO 210' TO DRILL AHEAD.
	16:30 - 0:00	7.50	DRLSUR	02	D	P		DRILL 11" HOLE ROTATE/SLIDE 210'-1,390' (1,180', 157'/HR). GPM 491. DH RPM 86 RPM=55, WOB 15-20K. PSI ON/OFF 1,260/1080. UP/DOWN/ ROT 61/48/54 K. DRAG 7 K. CIRC RESERVE W. 8.3# WATER.
11/21/2011	0:00 - 4:30	4.50	DRLSUR	02	D	P		DRILL 11" HOLE ROTATE/SLIDE 1,390'-1,870' (480', 107'/HR). GPM 491. DH RPM 86 RPM=55, WOB 15-20K. PSI ON/OFF 1,376/1,125. UP/DOWN/ ROT 77/54/63 K. DRAG 14 K. CIRC RESERVE W. 8.3# WATER. LOST RETURNS @ 1630' PUT AIR ON THE HOLE @ 1800 CFM.
	4:30 - 12:00	7.50	DRLSUR	02	D	P		DRILL 11" HOLE ROTATE/SLIDE 1,870'-2,430' (560', 75'/HR). TD @ 11/21/2011 12:00 GPM 491. DH RPM 86 RPM=55, WOB 15-20K. PSI ON/OFF 1,600/1,350. UP/DOWN/ ROT 81/60/70 K. DRAG 11 K. CIRC RESERVE W. 8.3# WATER. LAST SURVEY @ 2389' INC-19.21 AZ-350.60 APPROXIMATELY 3' HIGH 7.5' LEFT OF THE LINE.
	12:00 - 14:00	2.00	DRLSUR	05	A	P		CIRCULATE AND CONDITION HOLE FOR CASING RUN.
	14:00 - 17:30	3.50	DRLSUR	06	D	P		LDDS NO TIGHT WHILE LAYING DOWN DRILL STRING. LAY DOWN DIRECTIONAL TOOLS. PULL MOTOR AND BREAK BIT. LAY DOWN MOTOR.
	17:30 - 19:00	1.50	DRLSUR	12	A	P		MOVE PIPE RACKS AND CATWALK. PULL DIVERTER HEAD. RIG UP TO RUN CSG. AND MOVE CSG INTO POSITION TO P/U.
	19:00 - 21:30	2.50	DRLSUR	12	C	P		HOLD SAFETY MEETING. RUN 57 JTS OF 8-5/8" 28# J-55 LTC CSG. LAND FLOAT SHOE @ 2400.76' KB. LAND BAFFLE PLATE @ 2354.61' KB. MADE FLOAT SHOE UP WITH THREAD LOCK. RAN 5 TOTAL CENTRALIZERS.

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: PROPETRO 12/12, XTC 12/12

Event: DRILLING

Start Date: 10/19/2011

End Date: 1/14/2012

Active Datum: RKB @5,222.00usft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	21:30 - 22:00	0.50	DRLSUR	12	B	P		HOLD SAFETY MEETING, RUN 200' OF 1". RIG DOWN RIG MOVE OFF WELL, REBUILD DITCH. RIG UP CEMENT TRUCK, 2" HARD LINES, CEMENT HEAD, LOAD PLUG.
	22:00 - 23:30	1.50	DRLSUR	12	E	P		PRESSURE TEST LINES TO 2000 PSI. PUMP 135 BBLS OF WATER AHEAD. CATCH PSI. PUMP 20 BBLS OF 8.3# GEL WATER AHEAD. PUMP (300 SX) 61.4 BBLS OF 15.8# 1.15 YD 5 GAL/SK PREMIUM CEMENT W/ 2% CALC. DROP PLUG ON FLY. DISPLACE W/ 144 BBLS OF H2O. NO CIRC THROUGH OUT. FINAL LIFT OF 150 PSI AT 4 BBL/MIN. BUMP PLUG WITH 600 PSI. HELD 700 PSI FOR 5 MIN. FLOAT HELD.
	23:30 - 0:00	0.50	DRLSUR	12	E	P		PUMP (150 SX) 30.7 BBLS OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE NO CEMENT TO SURFACE. PUMP (150 SX) 30.7 BBLS OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE OF PREVIOUS WELL NO CEMENT TO SURFACE. SHUT DOWN AND CLEAN TRUCK.
11/22/2011	0:00 - 2:00	2.00	DRLSUR	12	E	P		WAIT 2 HOURS PUMP (75 SX) 15.3 BBLS OF SAME TAIL CEMENT W/ 4% CALC. CEMENT TO SURFACE. SHUT DOWN AND CLEAN TRUCK. WILL TOP OUT AFTER NEXT CEMENT JOB. RELEASE RIG @ 11/22/2011 02:00
1/6/2012	4:00 - 5:00	1.00	MIRU	01	C	P		PULL CAT WALK FORWARD. SKID RIG OVER HOLE. PLACE LOCK DOWN CAP ON PREVIOUS WELL. TAKE OFF CHOKE LINE. CENTER AND LEVEL RIG OVER HOLE. SET CAT WALK BACK IN PLACE.
	5:00 - 22:00	17.00	MIRU	14	A	P		SCREW ON LOCKDOWN FLANGE. SET DOWN STACK AND TIGHTEN UP STACK. CHECK RIG FOR CENTER. R/D ROT HEAD & FLOW NIPPLE INSTALL STRATA ROT HEAD / ATTEMPT TO INSTALL CHOKE VALVE AND ORBIT VALVE DID NOT FIT R/D VALVES INSTALL VALVES ONE AT A TIME FAB HOLE IN FLOOR PLATE AND INSTALLED ORBIT VALVE / FAB NEW FLOW LINE. NIPPLE UP FLOW LINE. WELD NEW FLANGE ON GAS BUSTER & FLOW NIPPLE R/U HARD LINE TO STRATA ROT HEAD & WELL HEAD. / WIRE IN NEW RECPT IN SER HOUSE FOR STRATA HPU HOUSE. R/U EQ LINE TIGHTEN ALL FLANGES. HAMMER UNION PREPAIR TO TEST.
	22:00 - 0:00	2.00	MIRU	15	A	P		HOLD SAFETY MEETING. TEST TOP DRIVE VALVE, FLOOR VALVE, DART VALVE, INSIDE AND OUTSIDE KILL LINE VALVES INSIDE CHOKE LINE VALVE, HCR VALVE, CHOKE LINE, CHOKE MANIFOLD VALVES AND CHOKES TO 5000 PSI FOR 10 MIN AND 250 PSI FOR 5 MIN. MIN AND 250 PSI FOR 5 MIN. TEST CSG TO 1500 PSI FOR 30 MIN. SPOOL IS NOT SEALING.

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: PROPETRO 12/12, XTC 12/12

Event: DRILLING

Start Date: 10/19/2011

End Date: 1/14/2012

Active Datum: RKB @5,222.00usft (above Mean Sea Level)

UWI: SE/NE/O/10/S/23/E/6/O/0/26/PM/N/2191/E/0/624/O/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
1/7/2012	0:00 - 11:30	11.50	MIRU	15	A	P		TEST TOP DRIVE VALVE, FLOOR VALVE, DART VALVE, PIPE AND BLIND RAMS, INSIDE AND OUTSIDE KILL LINE VALVES INSIDE CHOKE LINE VALVE, HCR VALVE, CHOKE LINE, CHOKE MANIFOLD VALVES AND CHOKES TO 5000 PSI FOR 10 MIN AND 500 PSI FOR 5 MIN. TEST ANNULAR TO 2500 PSI FOR 10 MIN AND 250 PSI FOR 5 MIN. TEST CSG TO 1500 PSI FOR 30 MIN. WORK ON PITS. HAD PROBLEMS WITH SPACER SPOOL NOT TESTING HAD TO GET TORK WRENCH TO TIGHTEN IT THEN THEN TESTED GOOD.
	11:30 - 12:00	0.50	PROD	07	A	P		SERVICE RIG TOP DRIVE CROWN / FUN TEST BOPS.
	12:00 - 14:30	2.50	DRLPRO	06	A	P		IN STALL WEAR BUSHING / P/U HUNTING 1.5 BH .21 RPG MOTOR AND MAKE UP MDI 616 BIT W/ 6-15. SCRIBE MOTOR AND MAKE UP DIRECTIONAL TOOLS. PROGRAM EM TOOL.
	14:30 - 18:00	3.50	DRLPRO	06	A	P		TRIP HWDP IN HOLE. INSTALL NEW STRATA ROT HEAD RUBBER.
	18:00 - 20:00	2.00	DRLPRO	09	A	P		CUT 286' DRILL LINE DO TO DAMAGE ON LINE.
	20:00 - 22:00	2.00	DRLPRO	06	A	P		TIH F/ 1115'-2165' TAGGED CMT @2165' FILL PIPE.
	22:00 - 23:30	1.50	DRLPRO	02	B	P		SPUD 1/7/2012@ 22:00. DRILL CEMENT AND FLOAT EQUIPMENT BAFFLE PLATE @ 2354' AND SHOE @ 2400'. RUN 480 GPM AND 40 RPM . W/10-16K ON BIT.
	23:30 - 0:00	0.50	DRLPRO	02	B	P		DRILL SLIDE 2441'-2468' (27', 54'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 1232/1003. TORQUE ON/OFF 7 / 8 K STRING WT UP/DOWN/ROT 70/60/60. 10 K DRAG FULL CIRC. RUNNING CENTRIFUGES. DRILLING W/ WATER. STRATA OFF LINE NO FLAIR.
1/8/2012	0:00 - 5:00	5.00	DRLPRO	02	B	P		DRILL SLIDE 2468'-3066 (598', 119.6'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 1230/1000. TORQUE ON/OFF 7 / 8 K STRING WT UP/DOWN/ROT 70/60/60. 10 K DRAG FULL CIRC. RUNNING CENTRIFUGES. DRILLING W/ WATER. STRATA OFF LINE NO FLAIR.
	5:00 - 5:30	0.50	DRLPRO	07	A			SERVICE TOP DRIVE TRAVELING BLOCKS.
	5:30 - 6:00	0.50	DRLPRO	02	B	P		DRILL SLIDE 3066-3112 (46', 9.2'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 1232/1003. TORQUE ON/OFF 7 / 8 K STRING WT UP/DOWN/ROT 70/60/60. 10 K DRAG FULL CIRC. RUNNING CENTRIFUGES. DRILLING W/ WATER. STRATA OFF LINE NO FLAIR.
	6:00 - 16:00	10.00	DRLPRO	02	B	P		DRILL SLIDE 3112-4201 (1089', 108'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 1890/1203. TORQUE ON/OFF 7 / 8 K STRING WT UP/DOWN/ROT 90/70/81. FULL CIRC. RUNNING CENTRIFUGES. DRILLING W/ WATER. STRATA OFF LINE NO FLAIR. 8.4 MUD WT 26 VIS.
	16:00 - 16:30	0.50	DRLPRO	07	A			SERVICE TOP DRIVE / CROWN FUN C-O-M.

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: PROPETRO 12/12, XTC 12/12

Event: DRILLING

Start Date: 10/19/2011

End Date: 1/14/2012

Active Datum: RKB @5,222.00usft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	16:30 - 0:00	7.50	DRLPRO	02	B	P		DRILL SLIDE 4201-5018 (817', 108'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 2305/1750. TORQUE ON/OFF 8 / 9 K STRING WT UP/DOWN/ROT 110/80/90. FULL CIRC. RUNNING CENTRIFUGES. DRILLING W/ WATER. STRATA OFF LINE NO FLAIR. 8.4 MUD WT 26 VIS.
1/9/2012	0:00 - 5:30	5.50	DRLPRO	02	B	P		DRILL SLIDE 5018-5654 (636', 115'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 2305/1750. TORQUE ON/OFF 8 / 9 K STRING WT UP/DOWN/ROT 110/80/90. FULL CIRC. RUNNING CENTRIFUGES. DRILLING W/ WATER. STRATA OFF LINE NO FLAIR. 8.4 MUD WT 26 VIS.
	5:30 - 6:00	0.50	DRLPRO	07	A	P		SERVICE TOP DRIVE TRAVELING BLOCKS.
	6:00 - 17:30	11.50	DRLPRO	02	B	P		DRILL SLIDE 5654-6697 (1043', 90'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 1870/2340. TORQUE ON/OFF 5 / 6 K STRING WT UP/DOWN/ROT 130/105/115. FULL CIRC. RUNNING CENTRIFUGES. DRILLING W/ WATER. STRATA OFF LINE NO FLAIR. 8.4 MUD WT 26 VIS.
	17:30 - 18:00	0.50	DRLPRO	07	A	P		SERVICE TOP DRIVE TRAVELING BLOCKS.CHECK C-O-M
	18:00 - 0:00	6.00	DRLPRO	02	B	P		DRILL SLIDE 6697-7210 (513', 85.5'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 2162/1922. TORQUE ON/OFF 5 / 6 K STRING WT UP/DOWN/ROT 160/105/125. FULL CIRC. RUNNING CENTRIFUGES. DRILLING W/ WATER. STRATA OFF LINE NO FLAIR. 8.6 MUD WT 26 VIS.
1/10/2012	0:00 - 5:00	5.00	DRLPRO	02	B	P		DRILL SLIDE 7210-7696 (486', 97.2'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 2162/1922. TORQUE ON/OFF 5 / 6 K STRING WT UP/DOWN/ROT 160/105/125. FULL CIRC. RUNNING CENTRIFUGES. DRILLING W/ WATER. STRATA OFF LINE NO FLAIR. 8.6 MUD WT 26 VIS.
	5:00 - 5:30	0.50	DRLPRO	07	A	P		SERVICE TOP DRIVE
	5:30 - 16:00	10.50	DRLPRO	02	B	P		DRILL SLIDE 7696-8376 (680', 64'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 2567/2150. TORQUE ON/OFF 9 / 7 K STRING WT UP/DOWN/ROT 160/110/135. FULL CIRC. DRILLING W/ WATER. STRATA ON LINE LINE FLAIR.15-20'DRILLING / 25' ON CONN. TRAP 200 PSI ON CONN 150 PSI DRILLING.
	16:00 - 16:30	0.50	DRLPRO	07	A	P		SERVICE TOP DRIVE
	16:30 - 21:30	5.00	DRLPRO	02	B	P		DRILL SLIDE 8376-8760 (384', 76'/HR) WOB 15-21K. AVE WOB-19K. RPM 50-60. SPM 115 GPM-517. ON/OFF PSI 2567/2150. TORQUE ON/OFF 9 / 7 K STRING WT UP/DOWN/ROT 160/110/135. FULL CIRC. DRILLING W/ WATER. STRATA ON LINE LINE FLAIR.15-20'DRILLING / 25' ON CONN. TRAP 200 PSI ON CONN 150 PSI DRILLING.

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: PROPETRO 12/12, XTC 12/12

Event: DRILLING

Start Date: 10/19/2011

End Date: 1/14/2012

Active Datum: RKB @5,222.00usft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	21:30 - 0:00	2.50	EVALPR	05	A	P		CIRC AND CONDITION HOLE. MUD WT IN 8.8 VIS 30. MUD WT OUT 8.8 VIS 30. / 25'-30' FLARE ON CONN. / DISP. H20 / WITH 11.3 MUD BUILD VOL / MUD WT FOR SHORT TRIP STRATA ON LINE HOLDING 150 PSI. 15' FLAIR.
1/11/2012	0:00 - 5:30	5.50	EVALPR	05	A	P		CIRC AND CONDITION HOLE. DISP. H20 / WITH 11.3 MUD BUILD VOL / MUD WT FOR SHORT TRIP STRATA ON LINE RAISING MUD WT TO 11.3 VIS 40
	5:30 - 9:30	4.00	EVALPR	05	A	P		CIRC AND CONDITION HOLE. RAISE MUD WT TO 11.3 VIS 40 STRATA OFF LINE. 5' FLAIR.
	9:30 - 10:00	0.50	EVALPR	07	A	P		RIG SERVICE TOP DRIVE.
	10:00 - 14:30	4.50	EVALPR	06	E	P		POOH PUMP DRY JOB. BLOW DOWN TOP DRIVE. WPER TRIP TO SHOE. HOLE TAKING PROPER FLUID. NO FLOW ON FLOW CHECKS. NO TIGHT
	14:30 - 20:30	6.00	EVALPR	06		P		TIH TO 5080' FILL DRILL PIPE, REAME THROUGH TIGHT SPOTS @ 5080' AND 5820', 6470.
	20:30 - 23:00	2.50	EVALPR	05	A	P		CIRC AND CONDITION HOLE.
	23:00 - 0:00	1.00	EVALPR	06	E	P		POOH FOR LOGS / PUMP DRY JOB. BLOW DOWN TOP DRIVE. HOLE TAKING PROPER FLUID. NO FLOW ON FLOW CHECKS.
1/12/2012	0:00 - 7:30	7.50	EVALPR	06	E	P		POOH FOR LOGS / PUMP DRY JOB. BLOW DOWN TOP DRIVE. HOLE TAKING PROPER FLUID. NO FLOW ON FLOW CHECKS.
	7:30 - 8:00	0.50	EVALPR	07	A	P		RIG SERVICE TOP DRIVE CROWN.
	8:00 - 12:00	4.00	EVALPR	11	E	Z		HELD S/M WITH LOGGERS R/U TO RUN WIRELINE LOGS. RUN TRIPLE-COMBO LOGS TO 5080' HIT BRIDGE / POOH R/D.
	12:00 - 21:30	9.50	EVALPR	06		Z		PICK UP BIT MAKE UP M.M TRIP IN BHA FOR WPER RUN TO 4640' FILL DRILL PIPE, REAME THROUGH TIGHT SPOTS @ 4640' AND 5097', 5135 AND 6775'.
	21:30 - 0:00	2.50	EVALPR	05	A	Z		TAG FILL @ 8613' -147' FILL WASH TO 8760'. CIRC AND CONDITION HOLE. RAISE MUD WT TO 11.5 VIS 40 STRATA OFF LINE. 25' FLAIR ON BOTTEMS UP.
1/13/2012	0:00 - 7:00	7.00	EVALPR	06	E	Z		POOH FOR LOGS / PUMP DRY JOB. BLOW DOWN TOP DRIVE. HOLE TAKING PROPER FLUID. NO TIGHT SPOTS HOLE IN GOOD SHAPE. NO FLOW ON FLOW CHECKS.
	7:00 - 10:00	3.00	EVALPR	11	E	Z		HELD S/M RIG UP TO RUN WIRE LINE LOGS. RUN IN HOLE TO 8725'
	10:00 - 15:00	5.00	EVALPR	11	E	P		RUN WIRE LINE LOGS. RUN IN HOLE TO 8725' LOG OUT RIG DOWN SAME.
	15:00 - 16:00	1.00	DRLPRO	12	A	P		HELD S/M WITH KIMZEY CASING & TUBULAR SOLUTIONS R/U TO RUN CASING. PULL WEAR BUSHING.
	16:00 - 16:30	0.50	DRLPRO	07	A	P		SERVICE TOP DRIVE TRAVLING BLOCKS.
	16:30 - 18:30	2.00	DRLPRO	12	A	Z		WAIT ON CABLE FOR FOR POWER TONGS.
	18:30 - 0:00	5.50	DRLPRO	12	C	P		RUN 4.5 PRODUCTION CASING.
1/14/2012	0:00 - 3:30	3.50	DRLPRO	12	C	P		RUN 4.5 CASING. 211 JOINTS 1 PUP JNT / 1 CROSSOVER JNT. WITH THE SHOE @ 8749.53 FC @ 8705.86
	3:30 - 4:00	0.50	CSG	05	A	P		CIRC OUT GAS. MUD WT 11.4 VIS 40. HOLD
	4:00 - 4:30	0.50	CSG	07	A	P		SAFETY MEETING AND RIG DOWN KIMZEY CSG. RIG SERVICE TOP DRIVE.

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: PROPETRO 12/12, XTC 12/12

Event: DRILLING

Start Date: 10/19/2011

End Date: 1/14/2012

Active Datum: RKB @5,222.00usft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	4:30 - 7:00	2.50	CSG	21	E	Z		WAITING ON BJ CEMENTERS.
	7:00 - 7:30	0.50	CSG	12	B	P		HELD S/M R/U BJ CEMENTERS.
	7:30 - 10:00	2.50	CSG	12	E	P		PRESSURE TEST TO 5000 PSI. PUMP 25 BBLs OF FRESH WATER. PUMP 170.08 BBLs (423 SX) OF 12.0 PPG 2.26 YD 12.48 GAL/SK OF LEAD CEMENT. PUMP 305 BBLs (1311 SX) OF 14.3# 1.31 YD 5.91 GAL/SK. POZ 50/50 TAIL CEMENT. SHUT DOWN AND FLUSH LINES. DROP PLUG AND DISPLACE W/ 135.5 BBLs OF FRESH WATER TREATED WITH CLAYFIX AND MAGNACIDE. FULL RETURNS WITH 10 BBLs OF WATER AND 1.5 BBLs CEMENT BACK. LIFT PSI OF 2550 / BUMP PLUG 3150 PSI. . PRESSURE HELD 5 MINS. FLOAT HELD. EST TOC FOR TAIL 3833". RIG DOWN CEMENTERS. FLUSH STACK WITH FRESH WATER. BLOW OUT MUD LINES.
	10:00 - 12:30	2.50	MIRU	14	A	P		HELD S/M WITH STRATA NIPPLE DOWN STRATA EQUIPMENT, ORBIT VALVE INSIDE CHOKE VALVE, ROT CLAMP.
	12:30 - 15:00	2.50	PRPSPD	14	A	P		NIPPLE DOWN FLOWLINE. P/U STACK. SET SLIPS UNDER STACK @ 95 K. CUT OF CSG. TRANSFER MUD. CLEAN SOLIDS OUT W/ SOLIDS CONTROL. (750 BBLs OF 11.4# MUD IN STORAGE AND 110 BBLs OF MUD STORED IN PILLTANK.) RELEASE RIG 1/4/2012 15:00.

1 General

1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

1.2 Well/Wellbore Information

Well	BONANZA 1023-6A3DS BLUE	Wellbore No.	OH
Well Name	BONANZA 1023-6A3DS	Wellbore Name	BONANZA 1023-6A3DS
Report No.	1	Report Date	3/16/2012
Project	UTAH-UINTAH	Site	BONANZA 1023-6H PAD
Rig Name/No.	SWABBCO 6/6	Event	COMPLETION
Start Date	3/16/2012	End Date	3/19/2012
Spud Date	11/20/2011	Active Datum	RKB @5,222.01ft (above Mean Sea Level)
UWI	SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0		

1.3 General

Contractor		Job Method		Supervisor	
Perforated Assembly		Conveyed Method			

1.4 Initial Conditions

Fluid Type		Fluid Density	
Surface Press		Estimate Res Press	
TVD Fluid Top		Fluid Head	
Hydrostatic Press		Press Difference	
Balance Cond	NEUTRAL		

1.5 Summary

Gross Interval	5,502.0 (ft)-8,635.0 (ft)	Start Date/Time	3/1/2012 12:00AM
No. of Intervals	38	End Date/Time	3/1/2012 12:00AM
Total Shots	192	Net Perforation Interval	54.00 (ft)
Avg Shot Density	3.56 (shot/ft)	Final Surface Pressure	
		Final Press Date	

2 Intervals

2.1 Perforated Interval

Date	Formation/ Reservoir	CCL@ (ft)	CCL-T S (ft)	MD Top (ft)	MD Base (ft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
3/1/2012 12:00AM	WASATCH/			5,502.0	5,504.0	4.00		0.360	EXP/	3.375	90.00			23.00 PRODUCTION N	

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (ft)	CCL-T S (ft)	MD Top (ft)	MD Base (ft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
3/1/2012 12:00AM	WASATCH/			5,606.0	5,607.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	WASATCH/			5,620.0	5,621.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	WASATCH/			5,740.0	5,742.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	WASATCH/			6,154.0	6,155.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	WASATCH/			6,169.0	6,170.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	WASATCH/			6,346.0	6,348.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	WASATCH/			6,416.0	6,418.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,202.0	7,203.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,220.0	7,221.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,270.0	7,271.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,283.0	7,284.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,330.0	7,332.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,396.0	7,397.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,414.0	7,415.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,514.0	7,515.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,544.0	7,546.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,594.0	7,597.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,720.0	7,721.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,740.0	7,741.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,778.0	7,779.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,813.0	7,816.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (ft)	CCL-T S (ft)	MD Top (ft)	MD Base (ft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
3/1/2012 12:00AM	MESAVERDE/			7,890.0	7,891.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,914.0	7,916.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,946.0	7,947.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			7,994.0	7,996.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,016.0	8,018.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,210.0	8,211.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,227.0	8,228.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,240.0	8,241.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,332.0	8,333.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,360.0	8,362.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,472.0	8,473.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,504.0	8,505.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,536.0	8,537.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,546.0	8,547.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,620.0	8,622.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
3/1/2012 12:00AM	MESAVERDE/			8,633.0	8,635.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	

3 Plots

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE				Spud Date: 11/20/2011					
Project: UTAH-UINTAH			Site: BONANZA 1023-6H PAD				Rig Name No: SWABBCO 6/6, SWABBCO 6/6		
Event: COMPLETION			Start Date: 3/16/2012					End Date: 3/19/2012	
Active Datum: RKB @5,222.01ft (above Mean Sea Level)				UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation	
3/1/2011	11:30 - 13:30	2.00	COMP	33		P		FILL SURFACE CSG. MIRU B&C QUICK TEST. PSI TEST T/ 1000 PSI. HELD FOR 15 MIN LOST 10 PSI. PSI TEST T/ 3500 PSI. HELD FOR 15 MIN LOST 49 PSI. 1ST PSI TEST T/ 7000 PSI. HELD FOR 30 MIN LOST 83 PSI. NO COMMUNICATION OR MIGRATION WITH SURFACE CSG BLEED OFF PSI. MOVE T/ NEXT WELL. SWIFW	
3/2/2011	7:00 - 10:00	3.00	COMP	37		P		PERF STG 1)PU 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH PERF AS PER PERF DESIGN. POOH. SWIFW	
3/12/2012	7:00 - 7:30	0.50	COMP	48		P		HSM, REVIEW WELL PLATT, FRAC DESIGN	

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: SWABBCO 6/6, SWABBCO 6/6

Event: COMPLETION

Start Date: 3/16/2012

End Date: 3/19/2012

Active Datum: RKB @5,222.01ft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:30 - 19:00	11.50	COMP	36	B	P		MIRU SUPERIOR [ROCK SPRINGS]
<p>PERF & FRAC FOLLOWING WELL AS PER DESIGN W/ 30/50 MESH SAND & SLK WTR. ALL CBP'S ARE HALIBURTON 8K CBP'S. REFER TO STIM PJR FOR FLUID, SAND AND CHEMICAL VOLUME PUM'D</p> <p>FRAC STG #1] WHP=1,492#, BRK DN PERFS=4,390#, @=3.8 BPM, INJ RT=49.2, INJ PSI=4,439#, INITIAL ISIP=2,504#, INITIAL FG=.73, FINAL ISIP=2,354#, FINAL FG=.71, AVERAGE RATE=48.2, AVERAGE PRESSURE=3,994#, MAX RATE=, MAX PRESSURE=, NET PRESSURE INCREASE=, 24/24 100% CALC PERFS OPEN. X OVER TO WIRE LINE</p> <p>PERF STG #2] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=8,392', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW</p> <p>FRAC STG #2] WHP=1,652#, BRK DN PERFS=4,355#, @=3.7 BPM, INJ RT=49, INJ PSI=5,012#, INITIAL ISIP=2,308#, INITIAL FG=.72, FINAL ISIP=2,341#, FINAL FG=.72, AVERAGE RATE=46, AVERAGE PRESSURE=3,900#, MAX RATE=49.9, MAX PRESSURE=6,267#, NET PRESSURE INCREASE=33#, 21/24 89% CALC PERFS OPEN. X OVER TO WIRE LINE</p> <p>PERF STG #3] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=8,048', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW</p> <p>FRAC STG #3] WHP=580#, BRK DN PERFS=3,779#, @=3.5 BPM, INJ RT=49.6, INJ PSI=3,950#, INITIAL ISIP=1,925#, INITIAL FG=.68, FINAL ISIP=1,912#, FINAL FG=.68, AVERAGE RATE=49.4, AVERAGE PRESSURE=3,469#, MAX RATE=50.1, MAX PRESSURE=5,742#, NET PRESSURE INCREASE=-13#, 24/24 100% CALC PERFS OPEN. X OVER TO WIRE LINE</p> <p>PERF STG #4] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=7,846', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW.</p> <p>FRAC STG #4] WHP=1,516#, BRK DN PERFS=2,998#, @=3.6 BPM, INJ RT=48.7, INJ PSI=4,822#, INITIAL ISIP=1,661#, INITIAL FG=.65, FINAL ISIP=1,862#, FINAL FG=.68, AVERAGE RATE=48.1, AVERAGE PRESSURE=3,903#, MAX RATE=50.2, MAX PRESSURE=5,590#, NET</p>								

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: SWABBCO 6/6, SWABBCO 6/6

Event: COMPLETION

Start Date: 3/16/2012

End Date: 3/19/2012

Active Datum: RKB @5,222.01ft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
								PRESSURE INCREASE=201#, 18/24 75% CALC PERFS OPEN. X OVER TO WIRE LINE
								PERF STG #5] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=7,627', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW. SWIFN.
3/13/2012	6:45 - 7:00	0.25	COMP	48		P		HSM, OPENING & CLOSING VALVES

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: SWABBCO 6/6, SWABBCO 6/6

Event: COMPLETION

Start Date: 3/16/2012

End Date: 3/19/2012

Active Datum: RKB @5,222.01ft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:00 - 18:00	11.00	COMP	36	B	P		<p>FRAC STG #5] WHP=1,549#, BRK DN PERFS=3,917#, @=3.8 BPM, INJ RT=49.6, INJ PSI=3,736#, INITIAL ISIP=2,197#, INITIAL FG=.73, FINAL ISIP=2,185#, FINAL FG=.73, AVERAGE RATE=49.3, AVERAGE PRESSURE=3,809#, MAX RATE=50.1, MAX PRESSURE=5,499#, NET PRESSURE INCREASE=-12#, 24/24 100% CALC PERFS OPEN. X OVER TO WIRE LINE</p> <p>PERF STG #6] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=7,362', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW</p> <p>FRAC STG #6] WHP=525#, BRK DN PERFS=2,583#, @=3.7 BPM, INJ RT=48.5, INJ PSI=3,827#, INITIAL ISIP=1,333#, INITIAL FG=.62, FINAL ISIP=2,237#, FINAL FG=.75, AVERAGE RATE=48.3, AVERAGE PRESSURE=3,680#, MAX RATE=51.7, MAX PRESSURE=5,398#, NET PRESSURE INCREASE=504#, 21/24 89% CALC PERFS OPEN. X OVER TO WIRE LINE</p> <p>PERF STG #7] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=6,448', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW</p> <p>FRAC STG #7] WHP=371#, BRK DN PERFS=2,782#, @=3.6 BPM, INJ RT=49.1, INJ PSI=4,229#, INITIAL ISIP=1,821#, INITIAL FG=.73, FINAL ISIP=2,111#, FINAL FG=.77, AVERAGE RATE=46.5, AVERAGE PRESSURE=3,629#, MAX RATE=49.9, MAX PRESSURE=6,419#, NET PRESSURE INCREASE=290#, 22/24 92% CALC PERFS OPEN. X OVER TO WIRE LINE</p> <p>PERF STG #8] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=5,772', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW</p> <p>FRAC STG #8] WHP=255#, BRK DN PERFS=1,735#, @=3.8 BPM, INJ RT=49.3, INJ PSI=3,690#, INITIAL ISIP=1,026#, INITIAL FG=.62, FINAL ISIP=1,500#, FINAL FG=.71, AVERAGE RATE=49.6, AVERAGE PRESSURE=3,183#, MAX RATE=50.2, MAX PRESSURE=4,524#, NET PRESSURE INCREASE=474#, 19/24 80% CALC PERFS OPEN. X OVER TO WIRE LINE</p> <p>P/U RIH W/ HALIBURTON 8K CBP, SET FOR TOP KILL @=5,452</p> <p>TOTAL FLUID PUMP'D=8,728 BBLs TOTAL SAND PUMP'D=195,240#</p>

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: SWABBCO 6/6, SWABBCO 6/6

Event: COMPLETION

Start Date: 3/16/2012

End Date: 3/19/2012

Active Datum: RKB @5,222.01ft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
3/16/2012	13:00 - 17:00	4.00	COMP	30		P		MOVE IN RU ND WELLHEAD NU BOPS PU POBS W/ 3-7/8" BIT TALLEY & PU TUBING, 4700' EOT SIW SDFW
3/19/2012	7:00 - 7:15	0.25	COMP	48		P		JSA= POWER SWIVEL SAFETY

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: SWABBCO 6/6, SWABBCO 6/6

Event: COMPLETION

Start Date: 3/16/2012

End Date: 3/19/2012

Active Datum: RKB @5,222.01ft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:15 - 17:00	9.75	COMP	30		P		<p>SIWP= 0 PSI CONTINUE TO RIH TAG PLUG @ 5452' RU DRILLING EQUIP EST CIRC PRESS TEST BOPS TO 3000#</p> <p>PLUG #1] DRILL THRU HALLI 8K CBP @ 5452' IN 15 MIN W/ 0 INCREASE (LOST CIRC)</p> <p>PLUG #2] CONTINUE TO RIH TAG SAND @ 5749' (20' FILL) C/O & DRILL THRU HALLI 8K CBP @ 5769' IN 9 MIN W/ 0 INCREASE REGAINED CIRC)</p> <p>PLUG #3] CONTINUE TO RIH TAG SAND @6423' (25' FILL) C/O & DRILL THRU HALLI 8K CBP @ 6448' IN 12 MIN W/50 # INCREASE</p> <p>PLUG #4] CONTINUE TO RIH TAG SAND @7351' (15' FILL) C/O & DRILL THRU HALLI 8K CBP @ 7366' IN 10 MIN W/100 # INCREASE</p> <p>PLUG #5] CONTINUE TO RIH TAG SAND @7602' (25' FILL) C/O & DRILL THRU HALLI 8K CBP @ 7627' IN 10 MIN W/100 # INCREASE</p> <p>PLUG #6] CONTINUE TO RIH TAG SAND @ 7816' (30' FILL) C/O & DRILL THRU HALLI 8K CBP @ 7846' IN 10 MIN W/ 100 # INCREASE</p> <p>PLUG #7] CONTINUE TO RIH TAG SAND @ 8023' (25' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8048' IN 9 MIN W/100 # INCREASE</p> <p>PLUG #8] CONTINUE TO RIH TAG SAND @ 8777' (15' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8392' IN 8 MIN W/100 # INCREASE (450# ON WELL)</p> <p>PBTD] CONTINUE TO RIH TAG SAND @ 8654' (50' FILL) C/O TO PBTD @ 8704' CIRC CLEAN PUH LD 17 JNTS LAND TUBING ON HNGER W/ 258 JNTS EOT @ 8190.19' RD PWR SW/L RD FLOOR & TUBING EQUIP ND BOPS NU WELLHEAD DROP BALL PUMP OFF BIT @ 2500# SIW TURN WELL OVER TO FBC RD RIG MOVE TO 6H2CS RU RIG</p> <p>LANDING DETAIL K.B.....15.00 HANGER.....86 258 JNTS 2-3/8" L-80.....8172.13 POBS.....2.20 EOT @.....8190.19</p> <p>TOTAL FLUID PUMPED.....8728 BBLS RIG REC.....2000 BBLS LEFT TO REC.....6728 BBLS</p> <p>CTAP DEL.....283 JNTS</p>

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud Date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig Name No: SWABBCO 6/6, SWABBCO 6/6

Event: COMPLETION

Start Date: 3/16/2012

End Date: 3/19/2012

Active Datum: RKB @5,222.01ft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	16:00 -		COMP	50				RIG USED.....258 JNTS RETURNED.....25 JNTS WELL TURNED TO SALES AT 1600 HR ON 3/19/2012 - 1200 MCFD, 1680 BWPD, FCP 2100#, FTP 1650#, 20/64 CK

1 General**1.1 Customer Information**

Company	US ROCKIES REGION
Representative	
Address	

1.2 Well Information

Well	BONANZA 1023-6A3DS BLUE	Wellbore No.	OH
Well Name	BONANZA 1023-6A3DS	Common Name	BONANZA 1023-6A3DS
Project	UTAH-UINTAH	Site	BONANZA 1023-6H PAD
Vertical Section	350.85 (°)	North Reference	True
Azimuth			
Origin N/S		Origin E/W	
Spud Date	11/20/2011	UWI	SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0
Active Datum	RKB @5,222.01ft (above Mean Sea Level)		

2 Survey Name**2.1 Survey Name: SURFACE**

Survey Name	SURFACE	Company	SCIENTIFIC DRILLING INTL
Started	11/20/2011	Ended	
Tool Name	EM	Engineer	Anadarko Employee

2.1.1 Tie On Point

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)
11.00	0.00	0.00	11.00	0.00	0.00

2.1.2 Survey Stations

Date	Type	MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)	TFace (°)
11/20/2011	Tie On	11.00	0.00	0.00	11.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
11/20/2011	NORMAL	191.00	0.11	128.61	191.00	-0.11	0.14	-0.13	0.06	0.06	0.00	128.61
	NORMAL	276.00	1.37	356.28	275.99	0.86	0.13	0.82	1.70	1.48	-155.68	-135.55
	NORMAL	360.00	3.14	352.68	359.92	4.14	-0.23	4.12	2.11	2.11	-4.29	-6.38
	NORMAL	450.00	5.16	352.23	449.68	10.59	-1.09	10.63	2.24	2.24	-0.50	-1.15
	NORMAL	540.00	7.01	352.65	539.17	20.05	-2.34	20.17	2.06	2.06	0.47	1.59
	NORMAL	630.00	9.13	349.82	628.28	32.53	-4.30	32.80	2.40	2.36	-3.14	-12.02
	NORMAL	720.00	10.67	349.27	716.93	47.74	-7.11	48.27	1.71	1.71	-0.61	-3.78
	NORMAL	810.00	12.45	348.67	805.11	65.44	-10.57	66.29	1.98	1.98	-0.67	-4.16
	NORMAL	900.00	13.54	349.54	892.80	85.32	-14.39	86.52	1.23	1.21	0.97	10.60
	NORMAL	990.00	14.86	349.42	980.05	107.02	-18.42	108.59	1.47	1.47	-0.13	-1.34
	NORMAL	1,080.00	14.97	348.77	1,067.02	129.77	-22.81	131.74	0.22	0.12	-0.72	-56.99
	NORMAL	1,180.00	15.56	349.32	1,163.49	155.62	-27.81	158.06	0.61	0.59	0.55	14.06
	NORMAL	1,260.00	15.80	350.21	1,240.51	176.89	-31.65	179.68	0.42	0.30	1.11	45.49
11/21/2011	NORMAL	1,350.00	15.93	348.51	1,327.08	201.07	-36.19	204.27	0.54	0.14	-1.89	-75.19
	NORMAL	1,440.00	16.19	348.88	1,413.57	225.49	-41.07	229.15	0.31	0.29	0.41	21.67
	NORMAL	1,530.00	16.70	347.34	1,499.89	250.42	-46.32	254.60	0.75	0.57	-1.71	-41.27
	NORMAL	1,620.00	17.09	347.70	1,586.01	275.95	-51.98	280.71	0.45	0.43	0.40	15.19
	NORMAL	1,710.00	17.98	349.18	1,671.82	302.52	-57.40	307.80	1.11	0.99	1.64	27.32

2.1.2 Survey Stations (Continued)

Date	Type	MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)	TFace (°)
11/21/2011	NORMAL	1,800.00	18.84	347.76	1,757.22	330.37	-63.09	336.19	1.08	0.96	-1.58	-28.22
	NORMAL	1,890.00	19.02	347.46	1,842.35	358.88	-69.35	365.34	0.23	0.20	-0.33	-28.54
	NORMAL	1,980.00	19.64	349.79	1,927.28	388.08	-75.22	395.11	1.10	0.69	2.59	52.31
	NORMAL	2,070.00	19.66	350.71	2,012.04	417.91	-80.35	425.37	0.34	0.02	1.02	86.73
	NORMAL	2,160.00	19.94	351.27	2,096.72	448.02	-85.12	455.86	0.38	0.31	0.62	34.38
	NORMAL	2,250.00	20.05	349.80	2,181.29	478.37	-90.18	486.63	0.57	0.12	-1.63	-78.35
	NORMAL	2,340.00	19.42	350.60	2,266.00	508.32	-95.36	517.01	0.76	-0.70	0.89	157.17
	NORMAL	2,400.00	19.21	350.60	2,322.63	527.90	-98.60	536.86	0.35	-0.35	0.00	180.00

2.2 Survey Name: Survey #1

Survey Name	Survey #1	Company	Anadarko Petroleum Corp
Started	1/7/2012	Ended	
Tool Name	MWD	Engineer	Anadarko Employee

2.2.1 Tie On Point

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)
2,400.00	19.21	350.60	2,322.63	527.90	-98.60

2.2.2 Survey Stations

Date	Type	MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)	TFace (°)
1/7/2012	Tie On	2,400.00	19.21	350.60	2,322.63	527.90	-98.60	536.86	0.00	0.00	0.00	0.00
1/8/2012	NORMAL	2,477.01	20.35	346.52	2,395.09	553.42	-103.79	562.88	2.32	1.48	-5.30	-52.39
	NORMAL	2,568.01	19.73	342.12	2,480.58	583.43	-112.19	593.84	1.79	-0.68	-4.84	-114.41
	NORMAL	2,658.01	19.56	334.92	2,565.36	611.53	-123.24	623.35	2.69	-0.19	-8.00	-97.40
	NORMAL	2,749.01	17.75	337.29	2,651.57	638.13	-135.06	651.49	2.16	-1.99	2.60	158.39
	NORMAL	2,840.01	17.58	341.33	2,738.29	663.94	-144.81	678.52	1.36	-0.19	4.44	99.82
	NORMAL	2,931.01	18.72	345.99	2,824.76	691.14	-152.75	706.63	2.03	1.25	5.12	54.09
	NORMAL	3,022.01	19.42	350.65	2,910.77	720.23	-158.74	736.31	1.84	0.77	5.12	67.52
	NORMAL	3,113.01	19.38	354.07	2,996.61	750.18	-162.76	766.52	1.25	-0.04	3.76	93.63
	NORMAL	3,203.01	17.80	350.91	3,081.91	778.62	-166.48	795.18	2.08	-1.76	-3.51	-148.97
	NORMAL	3,294.01	14.99	354.34	3,169.21	804.07	-169.83	820.84	3.26	-3.09	3.77	162.63
	NORMAL	3,385.01	13.97	359.44	3,257.32	826.77	-171.10	843.45	1.79	-1.12	5.60	131.11
	NORMAL	3,476.01	13.75	359.44	3,345.67	848.56	-171.32	865.01	0.24	-0.24	0.00	180.00
	NORMAL	3,567.01	12.61	359.67	3,434.27	869.31	-171.48	885.52	1.25	-1.25	0.25	177.48
	NORMAL	3,657.01	10.89	357.77	3,522.38	887.63	-171.87	903.67	1.96	-1.91	-2.11	-168.25
	NORMAL	3,748.01	7.95	355.39	3,612.14	902.50	-172.71	918.48	3.26	-3.23	-2.62	-173.63
	NORMAL	3,839.01	5.76	356.89	3,702.49	913.33	-173.46	929.29	2.41	-2.41	1.65	176.07
	NORMAL	3,930.01	5.45	7.43	3,793.06	922.18	-173.15	937.98	1.18	-0.34	11.58	111.96
	NORMAL	4,020.01	5.01	7.52	3,882.68	930.31	-172.08	945.84	0.49	-0.49	0.10	178.98
	NORMAL	4,111.01	5.23	358.73	3,973.32	938.40	-171.65	953.75	0.89	0.24	-9.66	-78.74
	NORMAL	4,202.01	3.72	353.19	4,064.04	945.48	-172.10	960.81	1.72	-1.66	-6.09	-166.78
	NORMAL	4,292.01	4.35	2.78	4,153.82	951.78	-172.28	967.07	1.02	0.70	10.66	51.82
	NORMAL	4,383.01	4.17	5.06	4,244.57	958.53	-171.82	973.65	0.27	-0.20	2.51	137.88
	NORMAL	4,474.01	5.10	1.99	4,335.27	965.86	-171.39	980.83	1.06	1.02	-3.37	-16.47
	NORMAL	4,564.01	4.66	2.16	4,424.94	973.52	-171.11	988.34	0.49	-0.49	0.19	178.20
	NORMAL	4,655.01	4.97	2.86	4,515.62	981.15	-170.77	995.82	0.35	0.34	0.77	11.08
	NORMAL	4,746.01	5.54	354.43	4,606.24	989.46	-171.00	1,004.06	1.05	0.83	-9.26	-57.81
	NORMAL	4,837.01	5.45	357.06	4,696.82	998.14	-171.65	1,012.74	0.29	-0.10	2.89	110.97
	NORMAL	4,928.01	4.66	356.36	4,787.47	1,006.15	-172.11	1,020.71	0.87	-0.87	-0.77	-175.88
1/9/2012	NORMAL	5,019.01	4.61	354.89	4,878.17	1,013.48	-172.68	1,028.04	0.16	-0.05	-1.84	-111.16
	NORMAL	5,109.01	4.31	0.23	4,967.90	1,020.46	-173.00	1,034.99	0.58	-0.33	6.16	127.59

2.2.2 Survey Stations (Continued)

Date	Type	MD (ft)	Inc (")	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (%/100ft)	Build (%/100ft)	Turn (%/100ft)	TFace (°)
1/9/2012	NORMAL	5,200.01	3.69	358.47	5,058.68	1,026.81	-173.07	1,041.26	0.69	-0.68	-1.93	-169.68
	NORMAL	5,291.01	2.90	2.69	5,149.53	1,032.04	-173.04	1,046.42	0.91	-0.87	4.64	165.03
	NORMAL	5,382.01	2.81	340.36	5,240.42	1,036.44	-173.68	1,050.87	1.22	-0.10	-24.54	-105.72
1/10/2012	NORMAL	5,472.01	2.37	342.47	5,330.32	1,040.29	-174.98	1,054.88	0.50	-0.49	2.34	168.83
	NORMAL	5,563.01	1.76	336.50	5,421.26	1,043.36	-176.10	1,058.09	0.71	-0.67	-6.56	-163.54
	NORMAL	5,654.01	2.26	349.33	5,512.21	1,046.41	-176.99	1,061.24	0.74	0.55	14.10	48.52
	NORMAL	5,745.01	1.49	345.11	5,603.16	1,049.32	-177.63	1,064.21	0.86	-0.85	-4.64	-171.94
	NORMAL	5,836.01	2.81	358.73	5,694.09	1,052.69	-177.98	1,067.60	1.55	1.45	14.97	28.06
	NORMAL	5,926.01	2.64	356.54	5,783.99	1,056.96	-178.16	1,071.84	0.22	-0.19	-2.43	-149.60
	NORMAL	6,017.01	2.07	342.83	5,874.92	1,060.63	-178.77	1,075.56	0.88	-0.63	-15.07	-142.05
	NORMAL	6,108.01	1.23	349.94	5,965.88	1,063.16	-179.42	1,078.16	0.95	-0.92	7.81	169.84
	NORMAL	6,199.01	2.55	352.30	6,056.83	1,066.13	-179.87	1,081.16	1.45	1.45	2.59	4.55
	NORMAL	6,289.01	2.86	1.46	6,146.73	1,070.35	-180.08	1,085.37	0.59	0.34	10.18	58.99
	NORMAL	6,380.01	1.67	8.66	6,237.65	1,073.93	-179.82	1,088.86	1.34	-1.31	7.91	170.13
	NORMAL	6,471.01	2.86	0.75	6,328.58	1,077.52	-179.59	1,092.36	1.35	1.31	-8.69	-18.69
	NORMAL	6,561.01	2.46	354.78	6,418.49	1,081.68	-179.74	1,096.50	0.54	-0.44	-6.63	-148.25
	NORMAL	6,652.01	1.45	13.32	6,509.43	1,084.75	-179.65	1,099.51	1.30	-1.11	20.37	156.98
	NORMAL	6,743.01	1.74	6.73	6,600.40	1,087.24	-179.22	1,101.91	0.38	0.32	-7.24	-35.64
	NORMAL	6,834.01	0.57	354.08	6,691.38	1,089.06	-179.11	1,103.69	1.31	-1.29	-13.90	-173.98
	NORMAL	6,924.01	0.54	24.13	6,781.37	1,089.90	-178.98	1,104.49	0.32	-0.03	33.39	110.77
	NORMAL	7,015.01	1.14	332.28	6,872.36	1,091.09	-179.22	1,105.71	1.00	0.66	-56.98	-79.62
	NORMAL	7,106.01	0.44	344.41	6,963.36	1,092.23	-179.74	1,106.91	0.79	-0.77	13.33	172.58
	NORMAL	7,197.01	0.48	16.39	7,054.35	1,092.93	-179.73	1,107.60	0.28	0.04	35.14	97.36
	NORMAL	7,287.01	0.79	350.21	7,144.35	1,093.90	-179.72	1,108.56	0.46	0.34	-29.09	-56.70
	NORMAL	7,378.01	1.27	4.45	7,235.33	1,095.53	-179.75	1,110.17	0.59	0.53	15.65	35.31
	NORMAL	7,469.02	1.14	7.26	7,326.31	1,097.43	-179.56	1,112.02	0.16	-0.14	3.09	156.96
	NORMAL	7,560.02	1.49	5.68	7,417.29	1,099.51	-179.33	1,114.03	0.39	0.38	-1.74	-6.70
	NORMAL	7,651.02	1.76	10.42	7,508.25	1,102.06	-178.96	1,116.49	0.33	0.30	5.21	28.85
	NORMAL	7,741.02	1.85	12.44	7,598.21	1,104.83	-178.40	1,119.14	0.12	0.10	2.24	36.27
	NORMAL	7,832.02	1.19	21.76	7,689.18	1,107.15	-177.73	1,121.32	0.77	-0.73	10.24	164.08
	NORMAL	7,923.02	1.05	15.34	7,780.16	1,108.83	-177.16	1,122.89	0.21	-0.15	-7.05	-141.31
	NORMAL	8,014.02	0.97	347.46	7,871.15	1,110.38	-177.11	1,124.42	0.54	-0.09	-30.64	-113.00
	NORMAL	8,105.02	0.04	22.73	7,962.14	1,111.17	-177.26	1,125.21	1.03	-1.02	38.76	178.59
	NORMAL	8,195.02	0.88	97.79	8,052.14	1,111.10	-176.56	1,125.04	0.97	0.93	83.40	77.60
	NORMAL	8,286.02	0.97	113.69	8,143.13	1,110.70	-175.17	1,124.42	0.30	0.10	17.47	78.74
	NORMAL	8,377.02	0.88	115.98	8,234.11	1,110.08	-173.83	1,123.60	0.11	-0.10	2.52	158.81
	NORMAL	8,467.02	1.27	124.24	8,324.10	1,109.22	-172.39	1,122.52	0.47	0.43	9.18	25.83
	NORMAL	8,558.02	1.58	125.12	8,415.07	1,107.93	-170.53	1,120.95	0.34	0.34	0.97	4.48
	NORMAL	8,649.02	1.54	141.73	8,506.04	1,106.25	-168.74	1,119.00	0.50	-0.04	18.25	103.32
	NORMAL	8,715.02	2.68	122.31	8,571.99	1,104.73	-166.89	1,117.21	2.02	1.73	-29.42	-42.05
1/14/2012	NORMAL	8,760.02	2.68	122.31	8,616.94	1,103.60	-165.11	1,115.81	0.00	0.00	0.00	0.00

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR McGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995
Address: P.O. Box 173779
city DENVER
state CO zip 80217 Phone Number: (720) 929-6304

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
Various	Ponderosa Wells						UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
	18421	18519				5/1/2012	
Comments: Move the attached wells into the Ponderosa unit. All wells are WSMVD. 11/16/2012							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

JAIME SCHARNOWSKE

Name (Please Print)

Signature

REGULATORY ANALYST

Title

11/8/2012

Date

RECEIVED

NOV 08 2012

Well Name	Quarter/Quarter	Section	Township	Range	APUI Number	County	New Entity Number	Formation
BONANZA 1023-6J2AS	NESW	6	10S	23E	4304751465	Uintah	18519	WSMVD
BONANZA 1023-6K1CS	NESW	6	10S	23E	4304751466	Uintah	18519	WSMVD
BONANZA 1023-6K2BS	NESW	6	10S	23E	4304751467	Uintah	18519	WSMVD
BONANZA 1023-6K2CS	NESW	6	10S	23E	4304751468	Uintah	18519	WSMVD
BONANZA 1023-6L2AS	NESW	6	10S	23E	4304751469	Uintah	18519	WSMVD
BONANZA 1023-6L2DS	NESW	6	10S	23E	4304751470	Uintah	18519	WSMVD
BONANZA 1023-6O1BS	SWSE	6	10S	23E	4304751473	Uintah	18519	WSMVD
BONANZA 1023-6O2DS	SWSE	6	10S	23E	4304751474	Uintah	18519	WSMVD
BONANZA 1023-6O3AS	SWSE	6	10S	23E	4304751475	Uintah	18519	WSMVD
BONANZA 1023-6P2BS	SWSE	6	10S	23E	4304751476	Uintah	18519	WSMVD
BONANZA 1023-6P3CS	SWSE	6	10S	23E	4304751478	Uintah	18519	WSMVD
BONANZA 1023-5J2DS	NESW	5	10S	23E	4304752063	Uintah	18519	WSMVD
BONANZA 1023-5K1BS	NESW	5	10S	23E	4304752064	Uintah	18519	WSMVD
BONANZA 1023-5K1CS	NESW	5	10S	23E	4304752065	Uintah	18519	WSMVD
BONANZA 1023-5K3DS	NESW	5	10S	23E	4304752066	Uintah	18519	WSMVD
BONANZA 1023-5L1DS	NESW	5	10S	23E	4304752067	Uintah	18519	WSMVD
BONANZA 1023-5L4AS	NESW	5	10S	23E	4304752068	Uintah	18519	WSMVD
BONANZA 1023-5L4DS	NESW	5	10S	23E	4304752069	Uintah	18519	WSMVD
BONANZA 1023-5O2AS	NESW	5	10S	23E	4304752070	Uintah	18519	WSMVD
BONANZA 1023-5E3BS	SWNW	5	10S	23E	4304752071	Uintah	18519	WSMVD
BONANZA 1023-5E3CS	SWNW	5	10S	23E	4304752072	Uintah	18519	WSMVD
BONANZA 1023-5L1AS	SWNW	5	10S	23E	4304752073	Uintah	18519	WSMVD
BONANZA 1023-5L3BS	SWNW	5	10S	23E	4304752074	Uintah	18519	WSMVD
BONANZA 1023-5M1AS	SWSW	5	10S	23E	4304752075	Uintah	18519	WSMVD
BONANZA 1023-5M1CS	SWSW	5	10S	23E	4304752076	Uintah	18519	WSMVD
BONANZA 1023-5M3BS	SWSW	5	10S	23E	4304752077	Uintah	18519	WSMVD
BONANZA 1023-5M3CS	SWSW	5	10S	23E	4304752078	Uintah	18519	WSMVD
BONANZA 1023-5N3CS	SWSW	5	10S	23E	4304752079	Uintah	18519	WSMVD
BONANZA 1023-5O4BS	SESE	5	10S	23E	4304752082	Uintah	18519	WSMVD
BONANZA 1023-5P1AS	SESE	5	10S	23E	4304752083	Uintah	18519	WSMVD
BONANZA 1023-5P1CS	SESE	5	10S	23E	4304752084	Uintah	18519	WSMVD
BONANZA 1023-5P4CS	SESE	5	10S	23E	4304752085	Uintah	18519	WSMVD
BONANZA 1023-5C4AS	NENW	5	10S	23E	4304752089	Uintah	18519	WSMVD
BONANZA 1023-5F2CS	NENW	5	10S	23E	4304752090	Uintah	18519	WSMVD
BONANZA 1023-5F3AS	NENW	5	10S	23E	4304752091	Uintah	18519	WSMVD
BONANZA 1023-5C2CS	NWNW	5	10S	23E	4304752092	Uintah	18519	WSMVD
BONANZA 1023-5D2DS	NWNW	5	10S	23E	4304752093	Uintah	18519	WSMVD
BONANZA 1023-5D3AS	NWNW	5	10S	23E	4304752094	Uintah	18519	WSMVD
BONANZA 1023-5E2AS	NWNW	5	10S	23E	4304752095	Uintah	18519	WSMVD
BONANZA 1023-6A1CS	NWNW	5	10S	23E	4304752096	Uintah	18519	WSMVD
BONANZA 1023-6I3AS	SWNW	5	10S	23E	4304752387	Uintah	18519	WSMVD
BONANZA 11-2	SWNW	11	10S	23E	4304734773	Uintah	18519	WSMVD
BONANZA 1023-6E4AS	SENE	6	10S	23E	4304751453	Uintah	18519	WSMVD
BONANZA 1023-6F1AS	SENE	6	10S	23E	4304751454	Uintah	18519	WSMVD
BONANZA 1023-6F1CS	SENE	6	10S	23E	4304751455	Uintah	18519	WSMVD
BONANZA 1023-6F4CS	SENE	6	10S	23E	4304751456	Uintah	18519	WSMVD
BONANZA 1023-6G2AS	SENE	6	10S	23E	4304751457	Uintah	18519	WSMVD
BONANZA 1023-6G4CS	SENE	6	10S	23E	4304751458	Uintah	18519	WSMVD
BONANZA 1023-6A3DS	SENE	6	10S	23E	4304751459	Uintah	18519	WSMVD
BONANZA 1023-6G1DS	SENE	6	10S	23E	4304751460	Uintah	18519	WSMVD
BONANZA 1023-6H1BS	SENE	6	10S	23E	4304751461	Uintah	18519	WSMVD
BONANZA 1023-6H2CS	SENE	6	10S	23E	4304751462	Uintah	18519	WSMVD
BONANZA 1023-6I2AS	SENE	6	10S	23E	4304751463	Uintah	18519	WSMVD
BONANZA 1023-6I3DS	SWSE	6	10S	23E	4304751471	Uintah	18519	WSMVD
BONANZA 1023-6J4AS	SWSE	6	10S	23E	4304751472	Uintah	18519	WSMVD
BONANZA 1023-6P3AS	SWSE	6	10S	23E	4304751477	Uintah	18519	WSMVD

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU33433
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: PONDEROSA
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-6A3DS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2191 FNL 0624 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 06 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047514590000
10. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		STATE: UTAH
TYPE OF SUBMISSION <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 6/1/2016 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </div> </div> <div style="text-align: right; margin-top: 10px;"> OTHER: <input style="width: 100px;" type="text"/> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between; align-items: flex-start;"> <div style="width: 60%;"> <p>The BONANZA 1023-6A3DS well was returned to production on 6/1/2016. Thank you.</p> </div> <div style="width: 35%; text-align: center;"> <p>Accepted by the Utah Division of Oil, Gas and Mining</p> <p>FOR RECORD ONLY</p> <p>June 09, 2016</p> </div> </div>		
NAME (PLEASE PRINT) Jennifer Thomas		PHONE NUMBER 720 929-6808
SIGNATURE N/A		TITLE Regulatory Specialist
DATE 6/9/2016		

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU33433			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: PONDEROSA			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-6A3DS			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2191 FNL 0624 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 06 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047514590000			
10. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		STATE: UTAH			
TYPE OF SUBMISSION <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/2/2016 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text" value="WORKOVER"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text" value="WORKOVER"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text" value="WORKOVER"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. A WELLBORE CLEANOUT HAS BEEN COMPLETED ON THE BONANZA 1023-6A3DS WELL. PLEASE SEE THE ATTACHED OPERATIONS SUMMARY REPORT FOR DETAILS.					
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY August 08, 2016					
NAME (PLEASE PRINT) Candice Barber		PHONE NUMBER 435 781-9749			
SIGNATURE N/A		TITLE HSE Representative			
DATE 8/8/2016					

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-6A3DS BLUE

Spud date: 11/20/2011

Project: UTAH-UINTAH

Site: BONANZA 1023-6H PAD

Rig name no.: ROCKY MOUNTAIN WELL SERVICE
3/3

Event: WELL WORK EXPENSE

Start date: 7/29/2016

End date: 8/2/2016

Active datum: RKB @5,222.00usft (above Mean Sea Level)

UWI: SE/NE/0/10/S/23/E/6/0/0/26/PM/N/2191/E/0/624/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
7/29/2016	9:00 - 10:30	1.50	MAINT	30	A	P		ROAD RIG F/ BON 1023-7N2AS. MIRU RIG & SPOT RIG EQUIP.
	10:30 - 12:00	1.50	MAINT	30	E	P		FWP = 63#. BLW WELL DWN. PUMP 10 BBLS DWN CSG. ND WH. UNLAND TBG, TBG NT STK. RELAND TBG. NU BOP. RU RIG FLOOR & TBG EQUIP. UNLAND WELL. LD TBG HNGR.
	12:00 - 17:00	5.00	MAINT	45	A	P		MIRU SCAN TECH. SCAN OOH W/ 258 JTS 2 3/8 I-80. 72 YB, 186 RB, HEAVY ID PITTING F/ 2282' - 8190' EOT, LIGHT OD SCALE F/ SURFACE - 8190' EOT, SL TOOLS STUCK IN JT 109 & 256 (COULD NOT GET THEM OUT OF JT), LAST 4 JTS PLUGGED W/ SAND & SCALE. BS, PLUNGER FOUND IN LAST JT. RDMO SCAN TECH. SWIFWE.
8/1/2016	6:45 - 7:00	0.25	MAINT	48	B	P		HSM/JSA
	7:00 - 14:30	7.50	MAINT	31	I	P		RIH W/ MILL, POBS, 72 JOINTS L-80, 6' PUP JOINT, & 198 JTS P-110. TAG FILL @ 8600'. 35' OF PERFS COVERED W/ FILL.
	14:30 - 19:00	4.50	MAINT	33	A	P		ESTABLISH CIRC W/ N2 UNIT. BEGIN C/O. MILL PLUGGED UP. BLOW DOWN WELL & SWAB TO CLEAR MILL. CIRC W/ N2 UNIT.
8/2/2016	6:45 - 7:00	0.25	MAINT	48	B	P		HSM/JSA
	7:00 - 12:00	5.00	MAINT	31	I	P		800 ON CSG & 710 ON TBG. KILL WELL. CONT RIH W/ PROD TBG & C/O TO 8,689'. CIRC WELL W/ N2 UNIT & POBS. LAND 257 JTS TBG @ 8182' & BROACH TBG.
	12:00 - 14:00	2.00	MAINT	33	A	P		BLOW WELL AROUND W/ N2 FOAM UNIT.
	14:00 - 16:00	2.00	RDMO	30	H	P		.RDMO & MOVE TO NEXT LOCATION.
8/3/2016	7:00 - 15:00	8.00	PROD	42		P		Arrived to location, rigged up and bleed pressure down on tubing. Started swabbing made 6 runs fluid level was at, 5200 ft, recovered 26 bbls. Well was on a suck most of the day, but towards the last runs it tried to blow little bit, tubing was pretty clean. shut well in and headed back to the shop
8/4/2016	7:00 - 15:00	8.00	PROD	42		P		Arrived to location, rigged up and bleed pressure down on tubing. Started swabbing made 8 runs fluid level was at, 5000 ft, recovered 50 bbls. Swabbed well back on, well unloaded for a while and operator dropped off a scale knocker by, so after unloading well for a while, we dropped the scale knocker in tubing and tried to trip it. It didnt come up, by then it was time to call it a day. Shut well in and headed back to the shop